

A Dark Energy Camera Search for an Optical Counterpart to the First Advanced LIGO Gravitational Wave Event GW150914

M. Soares-Santos¹, R. Kessler², E. Berger³, J. Annis¹, D. Brout⁴, E. Buckley-Geer¹, H. Chen², P. S. Cowperthwaite³, H. T. Diehl¹, Z. Doctor², A. Drlica-Wagner¹, B. Farr², D. A. Finley¹, B. Flaugher¹, R. J. Foley^{5,6}, J. Frieman^{1,2}, R. A. Gruendl^{5,7}, K. Herner¹, D. Holz², H. Lin¹, J. Marriner¹, E. Neilsen¹, A. Rest⁸, M. Sako⁴, D. Scolnic², F. Sobreira⁹, A. R. Walker¹⁰, W. Wester¹, B. Yanny¹, T. M. C. Abbott¹⁰, F. B. Abdalla^{11,12}, S. Allam¹, R. Armstrong¹³, M. Banerji^{14,15}, A. Benoit-Lévy^{16,11,17}, R. A. Bernstein¹⁸, E. Bertin^{16,17}, D. A. Brown¹⁹, D. L. Burke^{20,21}, D. Capozzi²², A. Carnero Rosell^{23,24}, M. Carrasco Kind^{5,7}, J. Carretero^{25,26}, F. J. Castander²⁵, S. B. Cenko^{27,28}, R. Chornock²⁹, M. Crocce²⁵, C. B. D’Andrea^{22,30}, L. N. da Costa^{23,24}, S. Desai^{32,31}, J. P. Dietrich^{32,31}, M. R. Drouot³, T. F. Eifler^{4,33}, J. Estrada¹, A. E. Evrard^{34,35}, S. Fairhurst³⁶, E. Fernandez²⁶, J. Fischer⁴, W. Fong³⁷, P. Fosalba²⁵, D. B. Fox³⁸, C. L. Fryer³⁹, J. Garcia-Bellido⁴⁰, E. Gaztanaga²⁵, D. W. Gerdes³⁵, D. A. Goldstein^{41,42}, D. Gruen^{20,21}, G. Gutierrez¹, K. Honscheid^{43,44}, D. J. James¹⁰, I. Karliner⁶, D. Kasen^{45,46}, S. Kent¹, N. Kuropatkin¹, K. Kuehn⁴⁷, O. Lahav¹¹, T. S. Li⁴⁸, M. Lima^{49,23}, M. A. G. Maia^{23,24}, R. Margutti⁵⁰, P. Martini^{43,51}, T. Matheson⁵², R. G. McMahon^{14,15}, B. D. Metzger⁵³, C. J. Miller^{34,35}, R. Miquel^{54,26}, J. J. Mohr^{32,31,55}, R. C. Nichol²², B. Nord¹, R. Ogando^{23,24}, J. Peoples¹, A. A. Plazas³³, E. Quataert⁵⁶, A. K. Romer⁵⁷, A. Roodman^{20,21}, E. S. Rykoff^{20,21}, E. Sanchez⁴⁰, V. Scarpine¹, R. Schindler²¹, M. Schubnell³⁵, I. Sevilla-Noarbe^{40,5}, E. Sheldon⁵⁸, M. Smith³⁰, N. Smith⁵⁹, R. C. Smith¹⁰, A. Stebbins¹, P. J. Sutton⁶⁰, M. E. C. Swanson⁷, G. Tarle³⁵, J. Thaler⁶, R. C. Thomas⁴², D. L. Tucker¹, V. Vikram⁶¹, R. H. Wechsler^{62,20,21}, J. Weller^{31,55,63}

(The DES Collaboration)

ABSTRACT

We report results of a deep search for an optical counterpart to the gravitational wave event GW150914, the first trigger from the Advanced LIGO gravitational wave detectors. We used the Dark Energy Camera (DECam) to image a 102 deg² area, corresponding to 38% of the initial trigger high-probability sky region and to 11% of the revised high-probability region. We observed in i and z bands at 4–5, 7, and 24 days after the trigger. The median 5σ point-source limiting magnitudes of our search images are $i = 22.5$ and $z = 21.8$ mag. We processed the images through a difference-imaging pipeline using templates from pre-existing Dark Energy Survey data and publicly available DECam data. Due to missing template observations and other losses, our effective search area subtends 40 deg², corresponding to 12% total probability in the initial map and 3% of the final map. In this area, we search for objects that decline significantly between days 4–5 and day 7, and are undetectable by day 24, finding none to typical magnitude limits of $i = 21.5, 21.1, 20.1$ for object colors $(i - z) = 1, 0, -1$, respectively. Our search demonstrates the feasibility of a dedicated search program with DECam and bodes well for future research in this emerging field.

Subject headings: binaries: close — catalogs — gravitational waves — stars: neutron — surveys

¹Fermi National Accelerator Laboratory, P. O. Box 500, Batavia, IL 60510, USA

²Kavli Institute for Cosmological Physics, University of Chicago, Chicago, IL 60637, USA

³Harvard-Smithsonian Center for Astrophysics, 60 Garden Street, Cambridge, MA, 02138

⁴Department of Physics and Astronomy, University of Pennsylvania, Philadelphia, PA 19104, USA

⁵Department of Astronomy, University of Illinois, 1002 W. Green Street, Urbana, IL 61801, USA

⁶Department of Physics, University of Illinois, 1110 W. Green St., Urbana, IL 61801, USA

⁷National Center for Supercomputing Applications, 1205 West Clark St., Urbana, IL 61801, USA

⁸STScI, 3700 San Martin Dr., Baltimore, MD 21218, USA

⁹Instituto de Física Teórica, Universidade Estadual Paulista, Rua Dr. Bento T. Ferraz 271, São Paulo, SP 01140-070, Brazil

¹⁰Cerro Tololo Inter-American Observatory, National Optical Astronomy Observatory, Casilla 603, La Serena, Chile

¹¹Department of Physics & Astronomy, University College London, Gower Street, London, WC1E 6BT, UK

¹²Department of Physics and Electronics, Rhodes University, PO Box 94, Grahamstown, 6140, South Africa

¹³Department of Astrophysical Sciences, Princeton University, Peyton Hall, Princeton, NJ 08544, USA

¹⁴Institute of Astronomy, University of Cambridge, Madingley Road, Cambridge CB3 0HA, UK

¹⁵Kavli Institute for Cosmology, University of Cambridge, Madingley Road, Cambridge CB3 0HA, UK

¹⁶CNRS, UMR 7095, Institut d'Astrophysique de Paris, F-75014, Paris, France

¹⁷Sorbonne Universités, UPMC Univ Paris 06, UMR 7095, Institut d'Astrophysique de Paris, F-75014, Paris, France

¹⁸Carnegie Observatories, 813 Santa Barbara St., Pasadena, CA 91101, USA

¹⁹Physics Department, Syracuse University, Syracuse, NY 13244

²⁰Kavli Institute for Particle Astrophysics & Cosmology, P. O. Box 2450, Stanford University, Stanford, CA 94305, USA

²¹SLAC National Accelerator Laboratory, Menlo Park, CA 94025, USA

²²Institute of Cosmology & Gravitation, University of Portsmouth, Portsmouth, PO1 3FX, UK

²³Laboratório Interinstitucional de e-Astronomia - LIneA, Rua Gal. José Cristino 77, Rio de Janeiro, RJ - 20921-400, Brazil

²⁴Observatório Nacional, Rua Gal. José Cristino 77, Rio de Janeiro, RJ - 20921-400, Brazil

²⁵Institut de Ciències de l'Espai, IEEC-CSIC, Campus UAB, Carrer de Can Magrans, s/n, 08193 Bellaterra,

Barcelona, Spain

²⁶Institut de Física d'Altes Energies (IFAE), The Barcelona Institute of Science and Technology, Campus UAB, 08193 Bellaterra (Barcelona) Spain

²⁷Astrophysics Science Division, NASA Goddard Space Flight Center, Mail Code 661, Greenbelt, MD 20771, USA

²⁸Joint Space-Science Institute, University of Maryland, College Park, MD 20742, USA

²⁹Astrophysical Institute, Department of Physics and Astronomy, 251B Clippinger Lab, Ohio University, Athens, OH 45701, USA

³⁰School of Physics and Astronomy, University of Southampton, Southampton, SO17 1BJ, UK

³¹Excellence Cluster Universe, Boltzmannstr. 2, 85748 Garching, Germany

³²Faculty of Physics, Ludwig-Maximilians-Universität, Scheinerstr. 1, 81679 Munich, Germany

³³Jet Propulsion Laboratory, California Institute of Technology, 4800 Oak Grove Dr., Pasadena, CA 91109, USA

³⁴Department of Astronomy, University of Michigan, Ann Arbor, MI 48109, USA

³⁵Department of Physics, University of Michigan, Ann Arbor, MI 48109, USA

³⁶School of Physics and Astronomy, Cardiff University, The Parade, Cardiff, CF24 3AA, UK

³⁷Steward Observatory, University of Arizona, 933 N. Cherry Avenue, Tucson, AZ 85721

³⁸Department of Astronomy & Astrophysics, Center for Particle & Gravitational Astrophysics, and Center for Theoretical & Observational Cosmology, Pennsylvania State University, University Park, PA 16802, USA

³⁹CCS Division, Los Alamos National Laboratory, Los Alamos, NM 87545

⁴⁰Centro de Investigaciones Energéticas, Medioambientales y Tecnológicas (CIEMAT), Madrid, Spain

⁴¹Department of Astronomy, University of California, Berkeley, 501 Campbell Hall, Berkeley, CA 94720, USA

⁴²Lawrence Berkeley National Laboratory, 1 Cyclotron Road, Berkeley, CA 94720, USA

⁴³Center for Cosmology and Astro-Particle Physics, The Ohio State University, Columbus, OH 43210, USA

⁴⁴Department of Physics, The Ohio State University, Columbus, OH 43210, USA

⁴⁵Departments of Physics and Astronomy, University of California, Berkeley

⁴⁶Lawrence Berkeley National Laboratory

⁴⁷Australian Astronomical Observatory, North Ryde, NSW 2113, Australia

⁴⁸George P. and Cynthia Woods Mitchell Institute for Fundamental Physics and Astronomy, and Department of Physics and Astronomy, Texas A&M University, College Station, TX 77843, USA

⁴⁹Departamento de Física Matemática, Instituto de Física, Universidade de São Paulo, CP 66318, CEP 05314-

1. Introduction

The advanced network of ground-based gravitational wave (GW) interferometers is designed to detect and study GW emission from events such as the mergers of binary systems composed of neutron stars and/or black holes to distances of hundreds of Mpc (see Abbott et al. 2013 and references therein). In mergers containing at least one neutron star, counterpart electromagnetic radiation is expected, potentially ranging from a short-duration gamma-ray burst through optical/near-IR emission from the radioactive decay of r-process nuclei to radio emission from ejecta interacting with the circumbinary medium (e.g., Li & Paczyński 1998; Nakar & Piran 2011; Metzger & Berger 2012; Barnes & Kasen 2013; Tanaka & Hotokezaka 2013; Tanaka et al. 2014; Aasi et al. 2014; Berger 2014; Cowperthwaite & Berger 2015). The detection of an electromagnetic counterpart will provide critical insight into the physics of the event, helping to determine the distance scale, energy scale, and the progenitor

environment, as well as insight into the behavior of matter post-merger (e.g., the production of jets and outflows).

With this motivation, we recently began an observational program using the wide-field Dark Energy Camera (DECam, Flaugh et al. 2015) on the Blanco 4-m telescope at Cerro Tololo Inter-American Observatory to search for optical counterparts to GW triggers from the new advanced GW detectors (LIGO, Abbott et al. 2009; Virgo, Acernese et al. 2009). This program was awarded three target of opportunity nights to observe LIGO-triggered events during the 2015B semester; observations were coordinated with and managed by the Dark Energy Survey (DES). Our program is optimized for detection of kilonovae, the hypothesized optical counterparts of mergers involving neutron stars, which would appear as red transients with expected decay timescale of about a week (for an overview of our program see Abbott et al. 2016b, section 5).

On 2015 September 14 at 09:50:45 UT the Advanced LIGO interferometer network detected a high significance candidate GW event designated GW150914 (Abbott et al. 2016) and two days later provided spatial location information in the form of probability sky maps via a private GCN circular (#18330, Singer et al. 2015). We initiated observations with DECam, a 3 deg² field-of-view instrument, on 2015 September 18 in an effort to identify an optical counterpart. Here we describe the observations and provide the results of the three-epoch search. These DECam observations are the deepest search for an optical counterpart to GW event GW150914 (Abbott et al. 2016a).

2. DECam Observations of GW150914

The detection of GW150914 was triggered by the cWB (coherent WaveBurst; Klimentenko et al. (2008)) unmodeled burst analysis during real-time data processing. On 2015 September 16, the LIGO Virgo Collaboration (LVC) provided two all-sky localization probability maps for the event, generated from the cWB and LALInferenceBurst (LIB; Veitch et al. (2015)) analyses. The cWB online trigger analysis makes minimal assumptions about signal morphology by searching for coherent power across the LIGO network. The LIB analysis is a version of the LALInference analysis Bayesian

970, São Paulo, SP, Brazil

⁵⁰Center for Cosmology and Particle Physics, New York University, 4 Washington Place, New York, NY 10003, USA

⁵¹Department of Astronomy, The Ohio State University, Columbus, OH 43210, USA

⁵²National Optical Astronomy Observatory, 950 North Cherry Avenue, Tucson, AZ, 85719

⁵³Columbia Astrophysics Laboratory, Pupin Hall, New York, NY, 10027, USA

⁵⁴Institució Catalana de Recerca i Estudis Avançats, E-08010 Barcelona, Spain

⁵⁵Max Planck Institute for Extraterrestrial Physics, Giessenbachstrasse, 85748 Garching, Germany

⁵⁶Department of Astronomy & Theoretical Astrophysics Center, University of California, Berkeley, CA 94720-3411, USA

⁵⁷Department of Physics and Astronomy, Pevensey Building, University of Sussex, Brighton, BN1 9QH, UK

⁵⁸Brookhaven National Laboratory, Bldg 510, Upton, NY 11973, USA

⁵⁹Steward Observatory, University of Arizona, 933 N. Cherry Ave., Tucson, AZ 85721, USA

⁶⁰School of Physics and Astronomy, Cardiff University, Cardiff, United Kingdom, CF24 3AA

⁶¹Argonne National Laboratory, 9700 South Cass Avenue, Lemont, IL 60439, USA

⁶²Department of Physics, Stanford University, 382 Via Pueblo Mall, Stanford, CA 94305, USA

⁶³Universitäts-Sternwarte, Fakultät für Physik, Ludwig-Maximilians Universität München, Scheinerstr. 1, 81679 München, Germany

forward-modeling-based follow up tool that uses a Sine-Gaussian signal morphology instead of models of compact binary mergers (Veitch et al. 2015); for information on both algorithms see Essick et al. (2015). The maps provided initial spatial localization of 50% and 90% confidence regions encompassing about 100 and 310 deg², respectively.

Our first observations with DECam took place on 2015 September 18 UT. Overall, we imaged 102 deg² covering 38% of the total probability in the initial cWB map; see Table 1 for a summary of our DECam observations. As shown in Figure 1, 18 deg², were centered on the LMC. For the remaining 84 deg² we obtained 3 separate epochs of imaging. At each epoch we acquired one 90-sec exposure in *i* band and two 90-sec exposures in *z* band. The first epoch spanned 4–5 days post-GW trigger (2015 September 18–19 UT), the second epoch 7 days post-GW trigger (2015 September 21 UT), and the third was obtained 24 days post-GW trigger (2015 October 08 UT).

Subsequently, in January 2016, the LVC released a revised sky map of localization probabilities from a LALInference analysis (GCN circular #18858, Singer et al. 2016). That analysis used the assumption that the signal arises from a compact binary coalescence (CBC). It also showed that the data are most consistent with models of a binary black hole merger (BBH). The LALInference-based map is considered the most accurate and authoritative localization for this event. Our 102 deg² cover a total of 11% probability in this new map, as the localization region has shifted significantly southward (see Figure 1) relative to the initial cWB map.

Our single-epoch exposures achieve median 5σ point-source limiting magnitudes of $i = 22.5$ and $z = 21.8$ with an rms variation among the images of ± 0.5 mag. This value is a consequence of night-to-night variations in the observing conditions (see Table 1) and of a strong gradient in stellar density and extinction along the major axis of the region imaged (see Figure 1).

2.1. Observing Strategy

We chose the location and sequence of DECam observations using an automated observing strategy algorithm. The algorithm takes two inputs: the peak *i*-band absolute magnitude of the hy-

pothesized source, and its distance. As our program was originally designed for kilonova searches, and the BBH nature of the event was unknown at the time of the observations, we chose a model compatible with the kilonova models of Barnes & Kasen (2013) and Grossman et al. (2014), with absolute magnitude $M_i = -11$ at peak, characteristic decay time of about 1 week and color $i-z = 1$. Since we did not have access to distance information for this event at the time, we used the nominal distance out to which LIGO was sensitive to binary neutron-star mergers: 60 Mpc. The two inputs, M_i and distance, are used to compute an apparent magnitude for the source. Then, assuming exposure time of 90 seconds (the nominal value used in all DES observations), we use the DES sky brightness model (Neilsen 2012), the atmospheric transmission model (using information on airmass and the interstellar dust extinction from Planck; Abergel et al. 2014), the expected seeing (from scaling laws with airmass and wavelength), and the confusion-limit probability model (based on stellar density maps) to compute, for each position in the sky, the probability that the hypothesized source would be detected by DECam. This DECam probability map is then multiplied by the LIGO-provided map to determine the region of interest for our observations. Deeper imaging is possible if called for by the model and distance.

Based on the final DECam $\times$ LIGO map, we observed the largest probability region available. The area covered had partial overlap with the DES footprint and was rising at the end of the night. The plan was to obtain 3 epochs of data covering the region of interest. Under the assumption that kilonovae are week-timescale decaying transients, we planned to take the first epoch as soon after the trigger as possible, the second epoch about 2 nights from the first, and the 3rd epoch 3 weeks later.

In the case of GW150914 the localization region intersected the Large Magellanic Cloud (LMC). The LMC region was disfavored by our algorithm due to the high-stellar density. To explore this region, we designed a separate program, which consisted of a set of short observations. We obtained 5-sec *i* and *z* band exposures covering 18 deg² centered on the LMC on 2015 September 18 and 27. This shallower data set was used to search for a potential failed supernova in the LMC; the results are

TABLE 1
SUMMARY OF OBSERVATIONS

Program	Night (UT)	MJD	Δt^a (days)	$\langle \text{PSF(FWHM)}_i \rangle$ (arcsec)	$\langle \text{airmass} \rangle$	$\langle \text{depth}_i \rangle$ (mag)	$\langle \text{depth}_z \rangle$ (mag)	A_{eff}^b (deg ²)
Main, 1 st epoch	2015-09-18	57383	3.88	1.38	1.50	22.71	22.00	52.8
	2015-09-19	57384	4.97	1.35	1.46	22.82	22.12	14.4
Main, 2 nd epoch	2015-09-21	57286	6.86	2.17	1.51	22.18	21.48	67.2
Main, 3 rd epoch	2015-10-08	57303	23.84	1.46	1.40	22.33	21.63	67.2
LMC, initial	2015-09-18	57383	3.98	1.14	1.30	21.32	20.62	14.4
LMC, extension	2015-09-27	57292	12.96	1.21	1.28	20.91	20.21	33.6

NOTE.—Summary of the observations performed in the “main” search program, described in this paper, and the “LMC” program, described in the companion paper Annis et al. (2016). We observed at high airmass because the region of interest was rising at the end of the night. The PSF FWHM, and therefore the actual depth achieved, are partly affected by these high airmass conditions. The reported depth corresponding to 5- σ point source detection in the search images. Variations in cloud conditions are also responsible for the variation in depth. The effective area imaged in the main program corresponds to 28 camera fields. The area covered in the LMC program totaled 20 fields.

^aTime elapsed between the trigger time and the time stamp of the first image of the night.

^bEffective area imaged, considering that approximately 20% of the 3 deg² field of view of DECam is lost due to chip gaps (10%), 3 dead CCDs (5%) and masked edge pixels (5%).

reported in a separate paper (Annis et al. 2016). Figure 1 shows a sky map computed for the end of the first night of observations, zoomed in to the region of interest and detailing the fields observed in each of the three epochs in red.

Our observing strategy is suitable for binary mergers that involve at least one neutron star. In particular, the choice of i and z filters is driven by the peculiar colors of kilonovae. For BBH events, we do not expect any optical emission unless the system has a significant accretion disk, which is unlikely for stellar mass black holes. For BBH events in the upcoming LIGO runs, we are investigating using bluer filters such as g and r to make our search less kilonova-specific.

2.2. Image Processing

Our data analysis relies on subtracting earlier template images from the science images taken for this program. In the area that overlaps the DES footprint (25% of the total), we used DES images from the first two seasons of the survey as templates. In the 75% of the area outside of the DES footprint, we used publicly available DECam data from the NOAO Science Archive (portal-nvo.noao.edu), requiring exposures of at least 30 sec in i and z bands.

We processed the DECam search and template images using the DES Data Management single-epoch image processing software (Desai et al. 2012; Mohr et al. 2012; Sevilla et al. 2011; Gruendl et al. 2016). Its output images were used as input to the difference imaging pipeline, which we developed from the DES Supernova pipeline (Kessler et al. 2015). The main adaptation of the pipeline for our purposes was to generalize to the case of search and template images with arbitrary relative alignment. A candidate requires two SExtractor (Bertin & Arnouts 1996) detections in the first epoch in both i and z bands. To reduce the large number of detected artifacts, each detection must satisfy quality requirements (Table 3 of Kessler et al. 2015) and be selected by our automated scanning program (Goldstein et al. 2015). For each of the 2349 candidate locations, “forced” PSF-fitted fluxes and uncertainties are obtained at every epoch regardless of whether or not there was a detection.

3. Analysis

While a BBH merger is not expected to result in an optical signature, it is nevertheless of interest to search for a possible optical counterpart. Our data was tailored for a kilonova search by choice




Fig. 1.— The color image shows the estimated limiting point-source magnitude for a 90-sec i band exposure as a function of sky position for our first night of DECam observations just before sunrise. In this area and for this time of night, the variations are mostly due to interstellar dust extinction. The dotted contours show the initial (September 2015) `skyprobcc_cWB_complete` map, while the solid contours are for the final (January 2016) `LALInference_skymap`. There is an island of significant probability in the Northern hemisphere in the `skyprobcc_cWB_complete` map, not present in the `LALInference_skymap`, so the dotted contours do not show the complete 50% or 90% areas. The hexagonal DECam fields observed are shown, with red for the main search and orange for the short exposure LMC data. Fields located on the west (left) side of the region of interest overlap with the DES area (footprint boundary shown in light-gold). The excluded region (dark grey) is beyond the horizon limit that could be observed with DECam at that time. The total area inside the camera pointings is about 102 deg². We covered about 11% of the total localization probability in the final map, and 38% of the initial map. The projection shown is an equal-area McBryde-Thomas flat-polar quartic projection.

of cadence and band passes. We refrained from using the key $i - z$ color cut for kilonova because the BBH nature of the merger does not call for it. We kept the assumption of a decaying transient. As our first epoch of observations occurred 4 days after the trigger, our prior on the search is that any candidate shall be fading slowly enough to be detectable 7 days after the event, but not 24 days after the event.

Of the 84 deg² area outside of the LMC, about

20% is lost due to camera fill-factor (see Table 1 for details) resulting in an effective area of 67.2 deg². In addition, 30% of the area is lost due to sparse availability of templates outside of the DES footprint. Another 10% loss arises from processing issues. This results in 40 deg² which were used in this analysis.

Based on an analysis of a sample of fake point sources injected into the images in this area, we find that the typical 80% source detection completeness in the subtracted images is at $i \approx 22.1$ and $z \approx 21.2$ mag. In the first epoch, where the observing conditions were better, we achieve that level of completeness at $i \approx 22.7$ and $z \approx 21.8$, comparable to the 5σ point source depth for those images. The fakes were in all the images we processed, thus the completeness depth reflects the variation in conditions as well.

3.1. Sample Selection

For the selection criteria described below, multiple observations per night (primarily in z band) are combined into a single weighted-average flux:

1. Second-epoch signal-to-noise ratio (S/N) above 2 in both i and z (to enable flux change determination with respect to the first epoch);
2. $\geq 3\sigma$ decline in both i and z fluxes from the first epoch to the second (to isolate fading sources; σ is defined by the quadrature sum of the flux errors in the first two epochs);
3. $S/N \leq 3\sigma$ in both i and z third epoch (at 24 days post-trigger, to reject long-timescale transients such as supernovae).

The above criteria are consistent with typical kilonova models. Since we do not apply any selection in color, they are also consistent with other transients with timescales of about 1-2 weeks. We are not sensitive to typical timescales of GRB afterglows, as our first observation happened 4 days after the trigger. The cadence and bandpasses of our data did not support further generalization of the search to other classes of transients.

3.2. Results

In Table 2 we show the impact of our selection criteria on the sample of candidates as a function

of the first epoch i -band magnitude. The decaying light curve requirement has the most impact in reducing the sample size. None of the candidates pass all the selection criteria. The area analyzed, 40 deg^2 , covers 3% of the localization probability in the final LALInference map (though it covered 12% in the initial cWB map).

To interpret these results some caveats are required. Because our selection criteria impose demands on significance in the second epoch, the actual first epoch search depth depends on the decline rate and $i - z$ color of the source model. In addition, we have not yet accounted for the degraded sensitivity to candidates located in bright galaxies.

For a particular source model, we can estimate the search depth. We applied our selection criteria to a sample of fake sources randomly placed in our search images before processing with our difference imaging pipeline. Our primary set of fakes are kilonova fakes, which we introduced using the light curves and spectra provided by Barnes & Kasen 2013. They have a constant decay rate of 0.3 mags/day and are red, with $(i - z) \approx 1$.

The magnitude at which we recover 50% of the fakes, $m_{50\%}$, is about 1 magnitude brighter than the 5σ point source limiting magnitude reported in Table 1, i.e., $m_{50\%} - m_{5\sigma} \approx -1$.

We did not impose color-based selection criteria but the choice of bandpasses implicitly does. Thus it is necessary to establish the performance of our analysis as a function of color, which we did by introducing fakes with similar timescale and brightness of the kilonova models, but with bluer colors. Simulations with bluer models show that for sources with $(i - z) = 0$ the search depth is $m_{50\%} - m_{5\sigma} \approx -1.4$; for $(i - z) = -1$, it is $m_{50\%} - m_{5\sigma} \approx -2.4$. We therefore achieve magnitude limit $i = 21.5, 21.1, 20.1$ for object colors $(i - z) = 1, 0, -1$, respectively.

4. Conclusions

We presented our search for an optical counterpart to the first gravitational wave event, GW150914, using the wide-field DECam instrument. Our observations cover 102 deg^2 corresponding to 11% of the total probability map. The search images used in this analysis reach median 5σ point source depth of $i = 22.5$ and $z = 21.8$

mag. Our DECam/Blanco observations are the deepest optical follow-up for this GW event.

Using selection criteria which isolate fading transients over the analysis region covering 3% of the total localization probability, we find no candidate counterparts. This result is not surprising given the partial areal coverage and the BBH merger nature of the event, which is not expected to produce any optical emission. However, the work establishes a very sensitive search program, capable of detecting week-timescale transients down to magnitude limit $i = 21.5, 21.1, 20.1$ for source colors $(i - z) = 1, 0, -1$, respectively. If there is an unexpected optical counterpart associated with BBH mergers detected by LIGO, our prospects for detection in the upcoming years are good.

Prospects are also good for future events involving neutron stars: were GW150914 a binary neutron star merger, our search would have been sensitive to some kilonova models ($M_i = -15$; Barnes & Kasen 2013) out to a distance of 200Mpc, which is about the nominal range that the GW detector network is expected to achieve in the next 3-5 years. For the more conservative model parameters that we used in the design of the observing strategy ($M_i = -11$; Grossman et al. 2014), our final analysis sensitivity reaches 30Mpc.

For the next observing campaign, we are investigating improved background rejection criteria using information such as: matching against a galaxy catalog to remove transients associated with high-redshift galaxies, angular separation between i and z exposures to reduce asteroids, and detailed simulations of supernovae and source models to better optimize selection requirements as well as the search strategy for future events. These improvements will allow us to perform a more sensitive search, and enable spectroscopic followup soon after the first epoch data is obtained.

Our search is a crucial first step and demonstrates the viability of DECam for deep optical follow-up of GW events.

Funding for the DES Projects has been provided by the U.S. Department of Energy, the U.S. National Science Foundation, the Ministry of Science and Education of Spain, the Science and

TABLE 2
NUMBER OF SELECTED EVENTS

mag(<i>i</i>)	raw	cut 1	cut 2	cut 3
18.0–18.5	84	1	0	0
18.5–19.0	177	1	0	0
19.0–19.5	291	2	0	0
19.5–20.0	227	2	1	0
20.0–20.5	156	17	2	0
20.5–21.0	225	42	3	0
21.0–21.5	334	84	2	0
21.5–22.0	756	159	1	0
22.0–22.5	1099	183	0	0
total	2349	491	9	0

Technology Facilities Council of the United Kingdom, the Higher Education Funding Council for England, the National Center for Supercomputing Applications at the University of Illinois at Urbana-Champaign, the Kavli Institute of Cosmological Physics at the University of Chicago, the Center for Cosmology and Astro-Particle Physics at the Ohio State University, the Mitchell Institute for Fundamental Physics and Astronomy at Texas A&M University, Financiadora de Estudos e Projetos, Fundação Carlos Chagas Filho de Amparo à Pesquisa do Estado do Rio de Janeiro, Conselho Nacional de Desenvolvimento Científico e Tecnológico and the Ministério da Ciência, Tecnologia e Inovação, the Deutsche Forschungsgemeinschaft and the Collaborating Institutions in the Dark Energy Survey.

The Collaborating Institutions are Argonne National Laboratory, the University of California at Santa Cruz, the University of Cambridge, Centro de Investigaciones Energéticas, Medioambientales y Tecnológicas-Madrid, the University of Chicago, University College London, the DES-Brazil Consortium, the University of Edinburgh, the Eidgenössische Technische Hochschule (ETH) Zürich, Fermi National Accelerator Laboratory, the University of Illinois at Urbana-Champaign, the Institut de Ciències de l’Espai (IEEC/CSIC), the Institut de Física d’Altes Energies, Lawrence Berkeley National Laboratory, the Ludwig-Maximilians Universität München and the associated Excellence Cluster Universe, the University of Michi-

gan, the National Optical Astronomy Observatory, the University of Nottingham, The Ohio State University, the University of Pennsylvania, the University of Portsmouth, SLAC National Accelerator Laboratory, Stanford University, the University of Sussex, and Texas A&M University.

The DES data management system is supported by the National Science Foundation under Grant Number AST-1138766. The DES participants from Spanish institutions are partially supported by MINECO under grants AYA2012-39559, ESP2013-48274, FPA2013-47986, and Centro de Excelencia Severo Ochoa SEV-2012-0234. Research leading to these results has received funding from the European Research Council under the European Unions Seventh Framework Programme (FP7/2007-2013) including ERC grant agreements 240672, 291329, and 306478.

This research uses services or data provided by the NOAO Science Archive. NOAO is operated by the Association of Universities for Research in Astronomy (AURA), Inc. under a cooperative agreement with the National Science Foundation.

REFERENCES

- Aasi, J. et al. 2014, *ApJS*, 211, 7
- Abbott, B. P. et al. 2013, *arXiv:1304.0670*
- Abbott, B. P. et al. 2016, *Phys. Rev. Lett.*, 116, 061102
- Abbott, B. P. et al. 2009, *Phys. Rev. D*, 80, 102001

- Abbott, B. P., et al. 2016a, ApJL submitted, arXiv:1602.08492
- Abbott, T. et al. 2016b, MNRAS submitted, arXiv:1601.00329
- Abergel, A. et al. 2014, A&A, 571, A11
- Acernese, F. et al. 2009, Classical and Quantum Gravity, 26, 085009
- Annis, J. et al. 2016, ApJL submitted, arXiv:1602.04199
- Barnes, J., & Kasen, D. 2013, ApJ, 775, 18
- Berger, E. 2014, ARA&A, 52, 43
- Bertin, E., & Arnouts, S. 1996, A&AS, 117, 393
- Cowperthwaite, P. S., & Berger, E. 2015, ApJ, 814, 25
- Desai, S. et al. 2012, ApJ, 757, 83
- Essick, R., Vitale, S., Katsavounidis, E., Vedovato, G., & Klimentko, S. 2015, ApJ, 800, 81
- Flaugher, B. et al. 2015, AJ, 150, 150
- Goldstein, D. A. et al. 2015, AJ, 150, 82
- Grossman, D., Korobkin, O., Rosswog, S., & Piran, T. 2014, MNRAS, 439, 757
- Gruendl, R., et al. 2016, in prep.
- Kessler, R. et al. 2015, AJ, 150, 172
- Klimentko, S., Yakushin, I., Mercer, A., & Mitselmakher, G. 2008, Classical and Quantum Gravity, 25, 114029
- Li, L.-X., & Paczyński, B. 1998, ApJ, 507, L59
- Metzger, B. D., & Berger, E. 2012, ApJ, 746, 48
- Mohr, J. J. et al. 2012, in Society of Photo-Optical Instrumentation Engineers (SPIE) Conference Series, Vol. 8451
- Nakar, E., & Piran, T. 2011, Nature, 478, 82
- Neilsen, Jr., E. H. 2012, in Astronomical Society of the Pacific Conference Series, Vol. 461, Astronomical Data Analysis Software and Systems XXI, ed. P. Ballester, D. Egret, & N. P. F. Lorente, 201
- Sevilla, I. et al. 2011, arXiv:1109.6741
- Singer, L., et al. 2015, GCN Circular, 18330
- Singer, L., et al. 2016, GCN Circular, 18858
- Tanaka, M., & Hotokezaka, K. 2013, ApJ, 775, 113
- Tanaka, M., Hotokezaka, K., Kyutoku, K., Wanajo, S., Kiuchi, K., Sekiguchi, Y., & Shibata, M. 2014, ApJ, 780, 31
- Veitch, J., et al. 2015, Phys. Rev., D91, 042003