


Superconducting Super Collider Laboratory



Contractor-Style Tunnel Cost Estimating

Don Scapuzzi, RTK Joint Venture

June 1990

CONTRACTOR-STYLE TUNNEL COST ESTIMATING*

Don Scapuzzi

Superconducting Super Collider Laboratory†
2550 Beckleymeade Ave.
Dallas, TX 75237

June 1990

*Presented at the Unique Underground Structures Symposium, Denver, CO, June 1990.

†Operated by the Universities Research Association, Inc., for the U.S. Department of Energy under Contract No. DE-AC02-89ER40486.

SUPERCONDUCTING SUPER COLLIDER

CONTRACTOR-STYLE TUNNEL COST ESTIMATING

by

Don Scapuzzi

RTK, Oakland, CA

ABSTRACT

Keeping pace with recent advances in construction technology is a challenge for the cost estimating engineer. Using an estimating style that simulates the actual construction process and is similar in style to the contractor's estimate will give a realistic view of underground construction costs.

For a contractor-style estimate, a mining method is chosen; labor crews, plant and equipment are selected, and advance rates are calculated for the various phases of work which are used to determine the length of time necessary to complete each phase of work. The durations are multiplied by the cost for labor and equipment per unit of time and, along with the costs for materials and supplies, combine to complete the estimate. Variations in advance rates, ground support, labor crew size, or other areas are more easily analyzed for their overall effect on the cost and schedule of a project.

TUNNEL CONSTRUCTION COST ESTIMATING

Modern tunneling methods are changing and improving rapidly. The innovations made in excavation machinery, i.e., tunnel boring machines (TBMs), and support systems, i.e., the New Austrian Tunnel Method (NATM) have revolutionized the industry in the last 20 years at a rate which is more rapid today than at any time in history. Creating a tunnel cost estimate that is current with the latest tunneling technology is a challenge that has to be met in the most realistic way available to the cost estimating engineer. The estimating

style needs to be as current as the tunneling method to be employed. This article describes a method similar to the procedure used by the tunnel contractor during the bidding phase of a project.

ESTIMATE TYPES

Estimating the cost of tunnel construction has traditionally been accomplished by one of two methods. The estimator may take the unit costs of pay items from previous contracts. He may expand or contract them in relation to the size of the current tunnel diameter and other geometric conditions. He should escalate the costs from the time of the previous construction to the time the planned construction. He may also have to make allowances for geotechnical conditions which are different from those which were encountered in the previous project.

This style of construction cost estimating is often employed by engineers. The accuracy of the estimate depends on the size and age of the available data base. This style does little to recognize the constant advances in modern tunneling or how changing conditions underground affect the cost of tunneling.

Another method the estimator may use is to break down the various elements of work into labor, equipment, materials, overhead, and profit. Each phase of the work effort is estimated in detail by determining the labor, equipment, materials, and time required to complete that phase. In this way, effects of changes in ground conditions, materials, quantities, and work methods are more realistically evaluated.

This style of construction cost estimating is most often employed by contractors. The accuracy of the estimate depends on the knowledge of the estimator and his construction experience. This style allows new methods and equipment to be incorporated into the process. The major divisions in a typical format are described below.

Basic Data

At the beginning of the estimate, the basic data used in all subsequent calculations is listed. This includes dimensions, assumed support methods, calculations of production rates and wage rates for the labor crafts.

Plant and Equipment

In this division, the costs for all facilities without a salvage value (site grading, roads, water treatment ponds) necessary to construct the project as well as materials and equipment which do have a salvage value (TBM, mucking system, miscellaneous shops and tools) are listed.

Direct Cost

The cost of direct labor, supplies, permanent materials, and subcontract items are calculated for the shafts, starter tunnel, main tunnel, and all concrete work.

Indirect Cost

This is a summary of project supervision, home office overhead, insurance, taxes, and all other costs not directly connected to any of the contract pay items.

Figure 1 is a flow chart for the methodology of a "contractor-style" estimate.

CREATING THE ESTIMATE

Each of the following tasks is interrelated with the other tasks, and the estimator continues to review decisions made in previous tasks as the estimate proceeds. The job layout has to be studied for all conditions which will have an effect on the work. This includes access to the job site, restrictions on working hours if the job site is in a city, weather patterns, and the availability of labor forces. Any special requirements set by the client must also be noted, such as completion time, portions of the job set for early beneficial occupancy, or owner-furnished equipment which is to be installed by the contractor.




FIGURE 1. ESTIMATING METHOD

The wage rates for the labor force and the working rules which will be in effect for the life of the project must also be determined. This information includes overtime rates, fringe benefits, workers' compensation, public liability and property damage insurance; federal, state and local taxes; and subsistence and travel pay. Local labor union offices are a good source for this information.

A geological review must be made which will be the controlling factor for estimating the daily progress once the mining is underway. All underground conditions which can be determined from subsurface exploration must be noted. The nature of the material to be removed has an effect on all construction operations, including excavation, muck handling, temporary or permanent support, and handling of water. The pace at which each of these operations takes place determines the overall progress and cost of the job.

A contractor-style estimate for a tunnel in Taylor Marl was selected as the example for this article. The mining method uses a Tunnel Boring Machine (TBM) equipped with tooth cutters. Segmental precast concrete liners with a flat invert section are used for initial support and need not be augmented for final lining.

The project includes a shaft at the starting point of the tunnel, and a 91-m-long "starter tunnel" in which the TBM and its trailing gear are assembled prior to the start of tunnel excavation. It is assumed that a second shaft has been constructed by others at the end of the project. When the TBM reaches this shaft, it is disassembled and removed through this shaft. The tunnel is then ready for construction of the final concrete floor.

SELECTING PLANT AND EQUIPMENT

Once the plans have been studied and the mining method is chosen, the plant and equipment can be selected. In this example, all new plant and equipment are assumed; however, in reality, a mix of new equipment and used equipment

from the contractors' yard will probably be selected. Included in plant and equipment are the general allowances for setting up the shops and offices, site grading, water treatment, etc.

ESTIMATING ADVANCE RATES

Estimating advance rates is one of the most important steps in contractor-style estimating. Here the estimator identifies the items of work appropriate to the planned construction method and estimates the time to complete each of them. During this process the estimator must also recognize and estimate any feature of the construction process which will delay the work.

Shaft and Starter Tunnel Excavation

The details of estimating the advance rates for the shaft and starter tunnel are shown in Figures 2 and 3. A detailed description of these estimates has been omitted from this paper for the sake of brevity, however, they are similar to the various steps described for the TBM tunnel.

TBM Tunnel Excavation

For tunnel excavation, everything which affects the progress of the excavation process must be identified (see Figure 4).

When a TBM is used, the instantaneous penetration rate must be estimated for each type of ground to be excavated (see Figure 5). These rates, in meters per hour, divided into the respective lengths of ground, determine the length of excavation time for the TBM.

The TBM operates on a 1.2-m-long stroke. At the end of each stroke, the cutter wheel is stopped and the hydraulic shove jacks which propel the TBM forward are retracted to begin the next "shove." This is called the regrip time and it is calculated for the length of the project.

If temporary support for the rock is required, installation time must also be totaled. This estimate uses a precast concrete segmental lining which serves as both the initial temporary support and the final lining.

RTK 12' ID TON TUNNEL
SSC PROJECT
ROCK UNIT COST MODEL WITH PRECAST LINER HOHL (TEXAS)

1990 DALLAS DOLLARS

1.60 ACCESS SHAFT DATA

1. DIAMETER (Finished Inside)	30 FT
a. SOFT GROUND	
- "A" Line	34 FT
- "B" Line	34 FT
b. ROCK	
- "A" Line	31 FT
- "B" Line	33.67 FT
2. DEPTH	
a. SOFT GROUND	30 LF
b. ROCK(SUPPORTED)	100 LF
c. ROCK(UNSUPPORTED)	20 LF
d. TOTAL DEPTH	150 LF
3. MUCK VOLUMES	
a. SOFT GROUND (BANK: to B Line)	33.6 CY/LF DEPTH
b. SOFT GROUND (EXCAVATED: 40% SWELL)	47.0 CY/LF DEPTH
c. ROCK (BANK: to B Line)	33.0 CY/LF DEPTH
d. ROCK (EXCAVATED: 60% SWELL)	52.0 CY/LF DEPTH
4. CONCRETE LINING VOLUMES	
a. SOFT GROUND (12 inches thick)	3.0 CY/LF DEPTH
b. ROCK (6" Shotcrete - Includes allowance to replace last 2' damaged by blasting & 20% for rebound)	3.2 CY/LF DEPTH
5. EXCAVATION CYCLE LENGTH	4 LF
6. EXCAVATION DURATION (See calculation adjacent)	
a. MOBILIZATION	2 DAYS
b. SOFT GROUND (DEPTH / PROGRESS/DAY)	7 DAYS
c. ROCK-SUPPORTED (DEPTH / PROGRESS/DAY)	33 DAYS
d. ROCK-UNSUPPORTED (DEPTH / PROGRESS/DAY)	6 DAYS
e. CONCRETE MOBILIZATION	2 DAYS
f. CONCRETE LINING	5 DAYS
g. TOTAL	55 DAYS

1.65 CALCULATION OF SHAFT EXCAVATION DURATION

	-----HOURS-----		
	ROCK	ROCK	SOFT GROUND
	SUPPORTED	UNSUPPORTED	

QUANTITY			
1. DRILL HOLES (Perimeter holes at 2.0 foot centers) + (1 burn hole and 4 starter holes) + (1 hole per 6.25 s.f. of surface area)	100		
2. # OF HYDRAULIC TRAC DRILLS = (1 DRILLS)	2		
3. HOLES PER DRILL = (40HOLES)	94		
4. DEPTH OF HOLE DRILLED (DEPTH PER CYCLE + 1 FT) = (FT)	5		
5. TOTAL DEPTH OF HOLES DRILLED BY EACH DRILL (6 HOLES X DEPTH) = (LF)	470		
6. DRILLING TIME @ 5LF/HR + 1 HR/HOLE SETUP TIME =	100	3.1	3.1
7. HOIST EQUIP IN & OUT OF SHAFT =		1.0	1.0
8. LOAD & SHOOT (4 HOLES/30 HOLES PER HOUR PER MINER-USE 3 MINERS) =		2.1	2.1 (*)
9. MUCK OUT:			
a. SOFT GROUND - (EXCAVATED CY/FT DEPTH) X (DEPTH PER CYCLE) / (20 CY/HR) =			9.4
b. ROCK - (EXCAVATED CY/FT DEPTH) X (DEPTH PER CYCLE) / (20 CY/HR) =	10.6	10.6	
10. SET STEEL AND LAGGING =			4.0
11. INSTALL ROCKBOLTS & SHOTCRETE	4.0	0.0	
TOTAL CYCLE TIME =	20.0	16.0	13.4
12. PROGRESS PER DAY (16 HOURS)			
a. SOFT GROUND: (16 HRS) / (CYCLE TIME) X (DEPTH/CYCLE) =			4.0 LF/DAY
b. ROCK(SUPPORTED): (16 HRS) / (CYCLE TIME) X (DEPTH/CYCLE) =			3.1 LF/DAY
c. ROCK(UNSUPPORTED): (16 HRS) / (CYCLE TIME) X (DEPTH/CYCLE) =			3.0 LF/DAY

(*) 30 MINUTES OF VENTILATION IS PROVIDED DURING LUNCH BREAK

FIGURE 2. ACCESS SHAFT DATA

RTK		12'10" TBM TUNNEL		1980 DALLAS DOLLARS				
SSC PROJECT		MARL (TEXAS)						
ROCK UNIT COST MODEL WITH PRECAST LINER								
1.70 STARTER TUNNEL DATA				1.75 CALCULATION OF STARTER TUNNEL EXCAVATION DURATION				
-----				-----				
1. TUNNEL SIZE (HORSESHOE)				QUANTITY				
-----				-----				
a. Finished Inside and "A" Line	18 FT	1. DRILL HOLES			87			
b. "B" Line	20.67 FT	(Perimeter holes at 2.0 foot centers)						
		(1 burn hole and 4 starter holes)						
		(1 hole per 6.25 sq. ft. of surface area)						
2. TUNNEL FACE AREA (Finished Inside)	289 SF	2. NUMBER OF HYDRAULIC TRAC DRILLS = (8 DRILLS)			2			
3. MUCK VOLUMES		3. HOLES PER DRILL = (8 HOLES)			44			
a. BANK (to B Line)	14.1 CY/LF	4. DEPTH OF HOLE DRILLED (DEPTH PER CYCLE + 1 FT) = (FT)			9			
b. EXCAVATED (60 % SUELL)	22.6 CY/LF	5. TOTAL LENGTH OF HOLES DRILLED BY EACH DRILL (8 HOLES) X (DEPTH) = (LF)			396			
4. LENGTH		6. MUCK VOLUME (CY/LF) X (CYCLE LENGTH) = (CY)			181			
a. WITH STEEL RIBS AND LAGGING	20 LF	7. MUCK TIME (3MIN/TRIP) X (CY) / (4CY/TRIP) = (MIN)			135.75			
b. WITH ROCKBOLTS	50 LF	8. CYCLE TIME (MINUTES)				RIBS & LAGGING	ROCK-BOLTS	M/O SUPPORT
c. WITHOUT SUPPORT	230 LF	- SET STEEL RIBS AND LAGGING			150	0	0	
d. TOTAL	300 LF	- MOVE DRILL IN			5	5	5	
5. EXCAVATION CYCLE LENGTH	8 LF	- INSTALL ROCKBOLTS AND CHAIN LINK FENCING			0	120	0	
6. EXCAVATION DURATION (See calculation adjacent)		- INSTALL SHOTCRETE			120	100	0	
a. MOBILIZATION	2 DAYS	- DRILL OUT (4 LF/MIN)			99	99	99	
b. RIBS AND LAGGING (LENGTH / PROGRESS)	2 DAYS	- LOAD HOLES (2 MIN/HOLE)/(2MEN LOADING)			87	87	87	
c. ROCKBOLTS (LENGTH / PROGRESS)	3 DAYS	- MOVE OUT			5	5	5	
d. WITHOUT SUPPORT (LENGTH / PROGRESS)	9 DAYS	- SHOOT AND VENT			30	30	30	
e. TOTAL	16 DAYS	- MOVE LOADER IN			5	5	5	
		- BAR DOWN			15	15	15	
		- MUCK OUT			135.75	135.75	135.75	
		- TOTAL CYCLE TIME (MINUTES)			651.75	601.75	301.75	
		- TOTAL CYCLE TIME (HOURS)			10.9	10.0	6.4	
		- CYCLES/22.5 HR DAY			2.1	2.3	3.5	
		- LF/DAY			16.0	18.4	20	

FIGURE 3. STARTER TUNNEL DATA

RTK		12" TO TBM TUNNEL				09-Feb-90	
SSC PROJECT		MARL (TEXAS)		1980 DALLAS DOLLARS		04:29 PM	
ROCK UNIT COST MODEL WITH PRECAST LINER						D. SCAPUZZI	
1.50 CALCULATION OF T.B.M. UTILIZATION RATE							
	QUANTITY	OTHER	PRODUCTION	QUANTITY	OTHER	PRODUCTION	
1. TBM EXCAVATION (TUNNEL LENGTH/ INSTANTANEOUS PENETRATION RATE) :			1042	12. WAITING FOR TRAINS (BUCKBOUND) (2% OF PRODUCTION TIME)	21		
2. TBM STROKE LENGTH = (LF/STROKE)	4			13. LUNCH: (30 MIN/SHIFT) X (16 SHIFTS/WEER) X (DURATION-WEEKS)	200		
3. REGRIP = TUNNEL LENGTH / STROKE LENGTH X 2 MIN/STROKE / 60 MIN/HR		200			3505	1042	
4. ALLOWANCE FOR UNFAVORABLE GROUND CONDITIONS: 22.5 HOURS / 1,000 L.F. :		563		TBM AVAILABILITY = (TOTAL HOURS - (*) HOURS) / TOTAL HOURS =			84%
5. INSTALL PRECAST LINER AND PER GRAVEL: TUNNEL LENGTH / 4 LF/RING @ 11 MIN/RING :		1146		TBM UTILIZATION RATE = PRODUCTION / TOTAL HOURS =			23%
6. ADD VENT LINE: TUNNEL LENGTH / 30 FT/MOVE X 10 MIN/MOVE / 60 MIN/HR :		139					
7. MAIN POWER:							
a. TUNNEL LENGTH / 1,000 FT/ CABLE/MOVE X 4 HRS/MOVE :		100					
b. OUTAGES: 1 EACH 26 WEEKS FOR 8 HRS :		16					
8. CUTTERS:							
a. ADDITIONAL TIME REQUIRED TO CHANGE CUTTERS (See calculation adjacent) :	(*)	0					
b. INSPECT 10 MIN/SHIFT X 10 SHIFTS/WEER X DURATION (WEEKS) / 60 MIN/HR :	(*)	50					
c. HISC CUTTER CHANGES: 1 /WEEK X 1.0 HRS/CHANGE X DURATION (WEEKS) :	(*)	35					
9. MAINTENANCE AND REPAIRS:							
a. ROUTINE MAINTENANCE: (2.0 HRS ON TUE-FRI) + (7.5 HRS ON SAT)	(*)	543					
b. OTHER: (DERAIL, ETC.): 2 HR/WEER		70					
10. START-UP: 2 WORKWEEKS		256					
11. MOISTING DELAY: 2 HR/WEER		70					

FIGURE 4. CALCULATION OF TBM UTILIZATION RATE

DS0449010

10

Scapuzzi

RTK	12'10" TBM TUNNEL		
SSC PROJECT			
ROCK UNIT COST MODEL WITH PRECAST LINER	MAAL (TEXAS)	1900 DALLAS DOLLARS	
=====			
1.30 CALCULATION OF TUNNEL EXCAVATION DURATION			
=====			
TRIAL EXCAVATION PERIOD :	177 DAYS	35 WEEKS	
CALCULATED EXCAVATION PERIOD :	177 DAYS		(72,000)
1. MATERIAL :	MAAL (TEXAS)		(2,000)
2. UNCONFINED COMPRESSIVE STRENGTH :	400 PSI :	3 MPa	
3. INSTANTANEOUS PENETRATION RATE :	24.0 FT/HR		
4. MACHINE UTILIZATION RATE :	25 % (See page 5)		
5. HOURS PER WORKWEEK :	120 HOURS		
6. AVERAGE DAILY ADVANCE RATE	141 FT/DAY		
7. EXCAVATION DURATION: (LENGTH) / (PROGRESS/DAY) :	177 DAYS		

09-Feb-90
04:29 PM
D. SCAPUZZI

FIGURE 5. CALCULATION OF TUNNEL EXCAVATION DURATION

After the 1.2-m-long segmental ring has been erected and fastened to the previously installed lining, the shove jacks are brought to bear against the lining and the next round of excavation begins.

As the excavation progresses, the utilities (electricity, compressed air, water, pump discharge), ventilation duct work, fans, and rails must be extended. Some of this work can be done concurrently with the excavation. The time it takes to accomplish the remainder is totaled for the length of the tunnel.

All maintenance time on the TBM must be estimated. Current practice is to spend one-half of the day shift the last four days of the week and one full shift on Saturday for preventative maintenance, repairs, and cutter changes. Additional time during the remainder of the work week is also allowed for inspecting the cutters and unscheduled TBM maintenance and repairs.

The muck handling cycle must be closely analyzed. Whenever the TBM is excavating, muck must be loaded into a muck handling system which is capable of receiving the muck as fast as it is being excavated. Whenever the muck handling system is incapable of receiving the muck, the excavating system becomes "muckbound" and the TBM is prevented from excavating. In the case of a rail muck handling system, being muckbound can be caused by an insufficient number of trains to complete the load-haul-dump-return cycle in time to keep a continuous supply of empty muck cars behind the TBM, equipment breakdowns, and derailments. This total amount of time must be estimated for the entire length of the project.

Any special geotechnical problems which are not accounted for in the regular computation of mining time should also be totaled. In this case, an allowance of one lost day per 300 m of tunnel was provided because of the lack of more complete data from subsurface investigations.

When a tunnel project is started there is a certain amount of time which is spent learning the whole excavation-mucking-support system. The inefficiency

of this start-up period must be accounted for. For this example, the crews will average only 50% efficiency in the first month. A start-up time of two weeks is used as time lost from production.

The time allowed for lunch on each shift is also calculated for the life of the project.

The excavation time for the TBM divided by the grand total of all excavation time plus non-production time gives the percentage of time that the TBM is working, or its "efficiency." The efficiency multiplied by the instantaneous penetration rate of the TBM multiplied by number of hours worked per week divided by the number of days per week which were spent excavating with the TBM equals the average daily progress for the TBM. The estimator should compare his calculated daily advance rate with similar-sized tunnels in similar types of ground for reasonable agreement and revise the assumptions if necessary.

The average daily advance rate divided into the length of tunnel to be mined gives the total length of time for direct excavation costs.

TUNNEL INTERIOR CONCRETE

The interior concrete is subdivided into six sections: (1) removal of the vent line, (2) initial cleanup, (3) pouring an invert in the tunnel, (4) pouring the floors of the hand-mined tunnels, (5) grouting the pea gravel installed between the segmental liner and the excavated ground, and (6) the final cleanup.

The progress rate for each of these items of work is based on past experience rather than on a detailed examination of the individual subdivisions since the work is relatively uniform from job to job.

Some phases of the concrete work overlap, resulting in a reduction of the total overall time used for maintenance and outside support costs. A schedule of the interior concrete work is shown in Figure 6.

DS0449013

13

Scapuzzi

RTX
 SSC PROJECT
 RDCK UNIT COST MODEL WITH PRECAST LINER
 12' ID TON TUNNEL
 NARL (TEXAS)
 1988 DALLAS DOLLARS

09-Feb-90
 04:29 PM
 D. SCAPUZZI

1.40 CALCULATION OF INTERIOR CONCRETE CONSTRUCTION DURATION

DESCRIPTION	QUANTITY	PROGRESS (LF/DAY)	MOBILIZE TIME (DAYS)	TOTAL DURATION (DAYS)
1. REMOVE VERT LINE	25,000 LF	7,500		4
2. INITIAL CLEANUP	25,000 LF	600		42
3. POUR INVERT	25,000 LF	450	3	59
4. POUR FLOORS OF HAND MINED TUNNELS	6,200 SF	3,000		2
5. PEA GRAVEL GROUT	25,000 LF	600		42
6. FINAL CLEANUP	25,000 LF	1,000		25
TOTAL DURATION (*)				174

(*) This work not accomplished in consecutive order.
 Some items overlap, resulting in a reduction of
 the time required for maintenance and outside
 support cost. For more information see the
 Construction Schedule. USE:

99 DAYS : 20 WEEKS

FIGURE 6. CALCULATION OF INTERIOR CONCRETE CONSTRUCTION DURATION

CALCULATING DIRECT COSTS

A crew is required for each underground task identified previously in determining advance rates. In addition, an outside support crew is also required to provide necessary support services such as mechanical and electrical maintenance, crane or hoist operation, and muck handling. The cost of wages and fringe benefits for the crews is totaled to establish the daily cost of direct labor (see Figures 7 and 8).

Next, the equipment to be used by both the underground and outside support crews is identified and this daily operational cost is totaled (see Figure 9).

Then, any routinely reoccurring miscellaneous costs are calculated, such as power, shop supplies, temporary support materials, and maintenance overtime. These can be calculated as a daily cost, a unit cost per lineal foot of work performed, or as a lump sum or subcontract price (see Figures 10 and 11).

The total direct costs for tunneling are summarized in Figure 12.

Direct Concrete Costs

The direct costs for the concrete operations are derived similarly to the direct tunneling costs. A discussion of these details has been omitted for the sake of brevity.

INDIRECT COSTS

The indirect crew consists of the project manager and his staff of supervisors and administrative personnel. Their salaries, taxes, and profit sharing are calculated as indirect labor costs.

General expenses are also part of the indirect costs and consist of monthly expenses such as office utilities and supplies as well as special consultant fees, the main office charges for support of the project, and other fees incurred by the project.

RTK 12' ID TBM TUNNEL
 SSC PROJECT
 ROCK UNIT COST MODEL WITH PRECAST LINER MARL (TEXAS) 1988 DALLAS DOLLARS
 09-Feb-90
 04:29 PM
 D. SCAPUZZI

ACCOUNT NUMBER	DESCRIPTION	QUANTITY	UNITS				TOTAL HOURS	LABOR RATE	LABOR & BURDEN	EQUIPMENT USAGE	MATERIAL	EQUIPMENT	CONTRACTOR'S ON & P	TOTAL
			HM	EV	DAI	EO								
6.00 DIRECT DAILY COSTS - TBM TUNNEL														
6.10 UNDERGROUND CREW														
HEADING CREW (3 SHIFTS PER DAY, 8 HOURS PER SHIFT)														
	SHIFTER (HM/DAY)	3 MEN	0			24	\$16.63	\$399	00	00	00	\$200	\$599	
	WINNERS (HM/DAY)	3 MEN	0			24	\$15.13	\$363	00	00	00	\$182	\$545	
(1)	MOTORMEN (HM/DAY)	5.4 MEN	0			43.2	\$17.30	\$751	00	00	00	\$375	\$1,126	
(2)	CALIF SWITCH OPERATOR (HM/DAY)	2.4 MEN	0			19.2	\$15.00	\$303	00	00	00	\$152	\$455	
	TBM OPERATOR (HM/DAY)	3 MEN	0			24	\$18.96	\$455	00	00	00	\$220	\$683	
	CONVEYOR OPERATOR (HM/DAY)	3 MEN	0			24	\$15.00	\$379	00	00	00	\$190	\$569	
	MECHANIC (HM/DAY)	3 MEN	0			24	\$18.96	\$455	00	00	00	\$220	\$683	
	CHAINMAN (HM/DAY)	1 MAN	0			8	\$17.30	\$139	00	00	00	\$70	\$209	
	INSTRUMENT MAN (HM/DAY)	1 MAN	0			8	\$17.30	\$139	00	00	00	\$70	\$209	
SUBTOTAL: HEADING CREW		24.0 MEN				190.4		\$3,384	00	00	00	\$1,692	\$5,076	
BULL GANG (1 SHIFT PER DAY, 8 HOURS PER SHIFT)														
	FOREMAN (HM/DAY)	1 MAN	0			8	\$11.35	\$91	00	00	00	\$45	\$136	
	LABORERS (HM/DAY)	3 MEN	0			24	\$18.61	\$235	00	00	00	\$127	\$382	
SUBTOTAL: BULL GANG		4 MEN				32		\$345	00	00	00	\$173	\$518	
SUBTOTAL: UNDERGROUND CREW		28.0 MEN				230.4		\$3,729	00	00	00	\$1,865	\$5,594	
SUBSISTENCE		28.0 MEN						\$0.00	00	00	00	00	00	
SMALL TOOLS, SAFETY, RUBBER, ETC.		28.0 MEN			\$13.00	0		00	00	\$374	00	00	\$374	
TOTAL DAILY DIRECT LABOR FOR UNDERGROUND CREW						230.4		\$3,729	00	\$374	00	\$1,865	\$5,968	
AVG. COST / MANHOUR		316.19												

(1) USE AN AVERAGE OF 1.8 MOTORMEN PER SHIFT OVER THE LENGTH OF THE JOB
 (2) USE AN AVERAGE OF 0.8 OPERATORS PER SHIFT OVER THE LENGTH OF THE JOB

FIGURE 7. DIRECT DAILY COSTS - TBM TUNNEL (UNDERGROUND CREW)

RTR		12' ID TBM TUNNEL													
SSC PROJECT						1980 DALLAS DOLLARS									
ROCK UNIT COST MODEL WITH PRECAST LINER		MARL (TEXAS)													
		UNITS													
ACCOUNT NUMBER	DESCRIPTION	QUANTITY	MH	EV	MAT	EO	TOTAL HOURS	LABOR RATE	LABOR & BURDEN	EQUIPMENT USAGE	MATERIAL	EQUIPMENT	CONTRACTOR'S OH & P	TOTAL	
6.20 OUTSIDE SUPPORT CREW (3 SHIFTS PER DAY, 8 HOURS PER SHIFT)															
	MECHANIC FOREMAN (HM/DAY)	1 MAN					8	917.21	9130	00	00	00	949	9297	
	MECHANICS (HM/DAY)	4 MEN					32	916.51	9528	00	00	00	9264	9792	
	ELECTRICAL FOREMAN (HM/DAY)	1 MAN					8	940.83	9327	00	00	00	9163	9490	
	ELECTRICIAN (HM/DAY)	3 MEN					24	939.85	9956	00	00	00	9470	91,434	
	LOADER OPERATOR (HM/DAY)	1 MAN					8	915.12	9121	00	00	00	946	9181	
	TOP & BOTTOM MAN (HM/DAY)	6 MEN					48	99.52	9457	00	00	00	9228	9485	
	CRANE OPERATOR (HM/DAY)	3 MEN					24	915.12	9363	00	00	00	9181	9544	
	CRANE OILER (HM/DAY)	3 MEN					24	915.12	9363	00	00	00	9181	9544	
	LABORERS (HM/DAY)	6 MEN					48	99.52	9457	00	00	00	9228	9485	
	TOOL ROOM ATTENDANT (HM/DAY)	1 MAN					8	99.52	976	00	00	00	930	9114	
	SUBTOTAL: OUTSIDE SUPPORT CREW	29 MEN					232		93,785	00	00	00	91,993	95,678	
	SUBSISTENCE	29 MEN						90.00	00	00	00	00	00	00	
	SMALL TOOLS, SAFETY, RUBBER, ETC.	29 MEN						913.00	00	00	9377	00	00	9377	
	TOTAL DAILY DIRECT LABOR FOR OUTSIDE SUPPORT CREW						232		93,785	00	9377	00	91,993	96,855	
	AVG. COST / HANNOUR	916.32													

FIGURE 8. DIRECT DAILY COSTS - TBM TUNNEL (OUTSIDE SUPPORT CREW)

RTK		12' ID TBM TUNNEL		1988 DALLAS DOLLARS										
SSC PROJECT		MARL (TEXAS)												
ROCK UNIT COST MODEL WITH PRECAST LINER														
ACCOUNT NUMBER	DESCRIPTION	QUANTITY	UNITS				TOTAL HOURS	LABOR RATE	LABOR & BURDEN	EQUIPMENT USAGE	MATERIAL	EQUIPMENT	CONTRACTOR'S ON & P	TOTAL
			HR	EU	MAT	EO								
6.30 EQUIPMENT DAILY OPERATING COST - TBM TUNNEL														
6.31 UNDERGROUND EQUIPMENT														
	LOCOMOTIVES: AVG 8 X SHIFTS X HR/SH	41 HR		815.00			0	00	8415	00	00	00	8415	
	MUCK CARS: AVG 8 X SHIFTS X HR/SH	504 HR		81.10			0	00	8554	00	00	00	8554	
	ALL OTHER CARS	1 LT		854.00			0	00	854	00	00	00	854	
	CALIFORNIA SWITCH: AVG 8 X 10 HR/DAY	8 HR		813.00			0	00	8104	00	00	00	8104	
	FANS: AVG 8 X SHIFTS X HR/SH	156 HR		81.30			0	00	8203	00	00	00	8203	
	PUMPS	1 LT		832.00			0	00	832	00	00	00	832	
	MISC. (ALLOWANCE)	1 LT		8107.00			0	00	8107	00	00	00	8107	
	SUBTOTAL: UNDERGROUND EQUIPMENT						0	00	81,649	00	00	00	81,649	
6.32 OUTSIDE EQUIPMENT														
	100 TON CRANE	10 HR		843.00			0	00	8774	00	00	00	8774	
	COMPRESSORS (2 EA)	10 HR		88.60			0	00	886	00	00	00	886	
	PUMPS	1 LT		832.00			0	00	832	00	00	00	832	
	LOADER	6 HR		827.00			0	00	8162	00	00	00	8162	
	HYDROCRANE	2 HR		821.00			0	00	842	00	00	00	842	
	FLATBED TRUCK	6 HR		811.00			0	00	866	00	00	00	866	
	SHOP & MISCELLANEOUS	1 LT		8215.00			0	00	8215	00	00	00	8215	
	ELEVATOR	6 HR		85.50			0	00	833	00	00	00	833	
	SUBTOTAL: OUTSIDE EQUIPMENT						0	00	81,410	00	00	00	81,410	
6.33 TUNNEL BORING MACHINE														
	A. OPERATION: BANK EXCAVATION X AVERAGE DAILY ADVANCE	652.00 CY		82.20			0	00	81,436	00	00	00	81,436	
	B. CUTTERS: (ALLOWANCE)			8100.00			0	00	8100	00	00	00	8100	
	C. TRAILING GEAR: 22.5 HR/DAY X UTILIZATION RATE =	5.16 HR		823.00			0	00	8119	00	00	00	8119	
	SUBTOTAL: TBM						0	00	81,655	00	00	00	81,655	

FIGURE 9. EQUIPMENT DAILY OPERATING COSTS - TBM TUNNEL

DS0449018

18

Scapuzzi

09-Feb-90
04:29 PM
D. SCAPUZZI

ATR		12' ID TBM TUNNEL												
SSC PROJECT		HARL (TEXAS)		1988 DALLAS DOLLARS										
ROCK UNIT COST MODEL WITH PRECAST LINER														
ACCOUNT NUMBER	DESCRIPTION	QUANTITY	UNITS				TOTAL HOURS	LABOR RATE	LABOR & BURDEN	EQUIPMENT USAGE	MATERIAL	EQUIPMENT	CONTRACTOR'S ON & P	TOTAL
			MM	EU	NAT	EO								
6.40 DIRECT MISCELLANEOUS COSTS - TBM TUNNEL														
6.41 ASSEMBLE & DISASSEMBLE TBM & TRAILING GEAR:														
a. LABOR: 12 MEN/SHIFT (40 SHIFTS TO ASSEMBLE) (30 SHIFTS TO DISASSEMBLE)		70 SHIFTS	96				6,720	816.19	8100,797	00	00	00	854,390	8163,195
b. EQUIPMENT USAGE & POWER:				8400.00			0		00	842,000	00	00	00	842,000
c. SUPPLIES, TOOLS, ECT.					8600.00		0		00	00	842,000	00	00	842,000
SUBTOTAL: ASSEMBLY AND DISASSEMBLY							6,720		8100,797	842,000	842,000	00	854,390	8247,195
6.42 MUCK DISPOSAL: (MUCK VOLUME M/SHELL) X (TUNNEL LENGTH)														
		204,000 CY		85.00			0		00	81,020,000	00	00	00	81,020,000
6.43 MAINTENANCE OVERTIME (SATURDAYS ONLY):														
a. LABOR: 12 MEN X DURATION (WEEKS)		35 SHIFTS	96				3,360	824.29	881,590	00	00	00	840,799	8122,396
b. POWER: 10,000 KWH/DAY X 80.00/KWH		35 DAYS		8000.00			0		00	820,000	00	00	00	820,000
c. SUPPLIES, TOOLS, ETC.		35 DAYS			8700.00		0		00	00	824,500	00	00	824,500
SUBTOTAL: MAINTENANCE OVERTIME							3,360		881,590	820,000	824,500	00	840,799	8174,896
6.44 PRECAST CONCRETE LINER														
		25,000 LF			8300.00		0		00	00	87,500,000	00	00	87,500,000

FIGURE 10. DIRECT MISCELLANEOUS COSTS - TBM TUNNEL

RTK SSC PROJECT ROCK UNIT COST MODEL WITH PRECAST LINER		12" ID TBM TUNNEL MARL (TEXAS)		1988 DALLAS DOLLARS											
ACCOUNT NUMBER	DESCRIPTION	QUANTITY	UNITS				TOTAL HOURS	LABOR RATE	LABOR & BURDEN	EQUIPMENT USAGE	MATERIAL	EQUIPMENT	CONTRACTOR'S ON & P	TOTAL	
			HR	CU	MAT	EQ									
6.50 DIRECT MISCELLANEOUS SUPPLIES - TBM TUNNEL															
	SHOP & ELECTRICAL SUPPLIES (0600/DAY) / (PROGRESS/DAY)	1 LF			84.26		0	00.00	00.00	84.26	00.00	00.00	84.26		
	MISC. SUPPLIES, HOSE, ETC.	1 LF			825.00		0	00.00	00.00	825.00	00.00	00.00	825.00		
	PEA GRAVEL	0.128 CY/LF			815.00		0	00.00	00.00	81.92	00.00	00.00	81.92		
	POWER														
	TBM: HP X AVAILABILITY % =	0 HP													
	COMPRESSORS: 0 X HP X 20% =	00 HP													
	FANS: AVG 0 X HP =	650 HP													
	SUBTOTAL HORSEPOWER	750 HP													
	HP X .76 X 24 HR/DAY /														
	0.8 POWER FACTOR	16,640 KWH													
	LIGHTS: 200W @ 40X AVG LENGTH =	1,500 KWH													
	PUMPS, SHOP, ETC. =	3,000 KWH													
	DAILY TOTAL	21,140 KWH													
	(KWH/DAY X 00.08/KWH) /	1 LF			813.21		0	00.00	00.00	813.21	00.00	00.00	813.21		
	AVERAGE DAILY ADVANCE														
	TOTAL MISC. SUPPLIES						0	00.00	00.00	844.39	00.00	00.00	844.39		

FIGURE 11. DIRECT MISCELLANEOUS SUPPLIES - TBM TUNNEL

DS0449019

19

Scapuzzi

RTK SSC PROJECT		12" ID TBM TUNNEL												09-Feb-90	
ROCK UNIT COST MODEL WITH PRECAST LINER		MARL (TEXAS)		1988 DALLAS DOLLARS										04:29 PM	
				D. SCAPUZZI											
ACCOUNT NUMBER	DESCRIPTION	QUANTITY	UNITS				TOTAL HOURS	LABOR RATE	LABOR & BURDEN	EQUIPMENT USAGE	MATERIAL	EQUIPMENT	CONTRACTOR'S O & P	TOTAL	
			HM	EV	NAT	EO									
6.60 DIRECT COST SUMMARY - TBM TUNNEL															
6.41	ASSEMBLE & DISASSEMBLE TBM & TRAILING GEAR	70 SHIFTS	96	\$600.00	\$600.00			6,720	\$16.19	\$108,797	\$42,000	\$42,000	00	\$54,398	\$247,195
6.10 & 6.31	EXCAVATION AT HEADING	177 DAYS	230.4	\$1,649.00	\$374.40			40,781	\$16.19	\$660,241	\$295,413	\$66,269	00	\$330,121	\$1,352,044
6.20 & 6.32	OUTSIDE SUPPORT	219 DAYS	232	\$1,410.00	\$377.00			50,008	\$16.32	\$829,107	\$300,790	\$82,563	00	\$414,593	\$1,635,133
6.33	TBM	177 DAYS		\$1,655.00				0		00	\$292,935	00	00	00	\$292,935
6.50	MISCELLANEOUS SUPPLIES	25,000 LF			\$44.39			0		00	00	\$1,109,750	00	00	\$1,109,750
6.42	MUCK DISPOSAL	204,000 CY			\$5.00			0		00	\$1,020,000	00	00	00	\$1,020,000
6.43	MAINTENANCE OVERTIME														
	a. LABOR	35 DAYS	96					3,360	\$24.29	\$81,590	00	00	00	\$40,799	\$122,389
	b. POWER	35 DAYS		\$800.00				0		00	\$20,000	00	00	00	\$20,000
	c. SUPPLIES	35 DAYS			\$700.00			0		00	00	\$24,500	00	00	\$24,500
6.44	PRECAST CONCRETE LINER	25,000 LF			\$300.00			0		00	00	\$7,500,000	00	00	\$7,500,000
TOTAL DIRECT COSTS FOR TBM TUNNEL								101,649		\$1,679,822	\$1,987,130	\$8,825,002	00	\$839,911	\$13,331,953

FIGURE 12. DIRECT COST SUMMARY - TBM TUNNEL

The costs for builders' risk insurance (0.2% of the contract value per year), bond (0.6% of contract value), and property taxes paid on plant and equipment are included in the indirect costs.

These indirect costs are typical for a large tunneling project. However, smaller projects require a much different mix of indirect costs and the cost estimator must take this into account.

SUMMARY OF TUNNEL COSTS

The summaries of each of the various categories are brought forward in the summary sheet (see Figure 13).

SENSITIVITY STUDIES

Once the estimating format has been established, sensitivity studies can easily be performed on any phase of the project, especially if the estimate is computerized (the author used a Lotus Symphony spreadsheet).

Labor rates, support methods, or crew sizes can be changed, and their effect on the total project cost and schedule can quickly be analyzed. Another exercise might be to substitute a used TBM with a lower net cost and shorter mobilization time but a slower advance rate and more maintenance costs.

One of the most valuable features for sensitivity studies is the effect of an unforeseen changed ground condition. With the example used for this article, incremental delays of from one day to 20 days were added for passing through an area of material that was harder than anticipated. No extra materials or supplies were used. The results of this change are shown in Figure 14.

Because of the ability to study changed conditions in a more realistic manner, the contractor-style estimate is also useful to the construction manager. Actual job conditions can be loaded into the format and the effect of change orders or changing ground conditions can be more easily understood by

RTK		12' ID TBM TUNNEL												09-Feb-90	
SSC PROJECT		MAAL (TEXAS)		1988 DALLAS DOLLARS										04:29 PM	
ROCK UNIT COST MODEL WITH PRECAST LINER														D. SCAPUZZI	
ACCOUNT NUMBER	DESCRIPTION	QUANTITY	UNITS				TOTAL HOURS	LABOR RATE	LABOR & BURDEN	EQUIPMENT USAGE	MATERIAL	EQUIPMENT	CONTRACTOR'S		AMOUNT FOR CHANGED CONDITIONS
			IN	EU	MT	EQ							ON & P	TOTAL	
1.00 SUMMARY TUNNEL COSTS															

3.50 PLANT AND EQUIPMENT COSTS						0		00	010,231,270		00	03,049,075	00	07,102,195	07,102,195
4.50 ACCESS SHAFT						9,600		0135,133	0154,715	0270,474		00	047,544	0427,000	0427,000
5.00 STARTER TUNNEL						5,432		003,201	003,010	0129,496		00	041,601	0337,300	0337,300
6.00 DIRECT TUNNEL COSTS						101,669		01,679,022	01,907,130	00,025,002		00	0039,911	013,331,953	013,331,953
7.00 OMITTED															
8.00 DIRECT CONCRETE COSTS						52,304		0022,112	0374,050	01,455,127		00	0411,056	03,063,145	03,063,145
9.00 INDIRECT TUNNEL COSTS						56,400		01,200,354	01,004,435		00	00	0640,277	03,005,266	03,005,266
TOTALS								04,000,023	013,915,410	010,600,170		03,049,075	02,000,411	027,547,755	027,547,755

FIGURE 13. SUMMARY TUNNEL COSTS

SENSITIVITY STUDY - 25,000 FOOT TUNNEL

DELAY BY DAYS vs COST




FIGURE 14. SENSITIVITY STUDY

the construction manager and owner. This is especially useful if underground conditions are encountered which were not anticipated and provided for in the bid documents and a claim for extra compensation is submitted by the contractor.

CONCLUSIONS

The assumptions made in this example are intended to develop a budget estimate for the client and not to be the "Low Bid." Far more elaborate detail is required for a true contractor's estimate.

Albert D. Parker, "Planning and Estimating Underground Construction" (1970).