

The LHC : Performance and Plans

BLOIS 2010


Lucio Rossi

Magnet and Superconductor Group Leader

CERN Geneva



Topics



- **The LHC(reminder)**
- **The last 18 months (rapidly)**
 - **The Accident, Repair and Consolidation**
 - **Initial Commissioning with Beam**
- **Plans**
 - **Near future (2010-2011)**
 - **Medium future (2012-16) Nominal LHC**
 - **Far future (2014-2020?) HL-LHC**
 - **Very far future (2030??) HE-LHC**




The LHC

Superconducting Proton Accelerator and Collider
installed in a 27km circumference underground tunnel (tunnel cross-
section diameter 4m) at **CERN**
Tunnel was built for LEP collider in 1985






LHC: Some Technical Challenges



Circumference (km)	26.7	100-150m underground
Number of superconducting twin-bore Dipoles	1232	Cable Nb-Ti, cold mass 37million kg
Length of Dipole (m)	14.3	
Dipole Field Strength (Tesla)	8.3	Results from the high beam energy needed
Operating Temperature (K) (cryogenics system)	1.9	Superconducting magnets needed for the high magnetic field Super-fluid helium
Current in dipole sc coils (A)	11850	Results from the high magnetic field 1ppm resolution
Beam Intensity (A)	0.5	$2.2 \cdot 10^{-6}$ loss causes quench
Beam Stored Energy (MJoules)	362	Results from high beam energy and high beam current 1MJ melts 1.5kg Cu
Magnet Stored Energy (MJoules)/octant	1100	Results from the high magnetic field
Sector Powering Circuit	8	1612 different electrical circuits



Interconnections




During cool-down of the LHC the machine contracts by **80 metres, 10m per octant**

- Vacuum continuity
- Electrical connections




Accident of September 19th 2008




- Following a very impressive start-up with beam on September 10, 2008
 - During a few days period without beam
 - Making the last step of dipole circuit in sector 34, to 9.3kA
 - At 8.7kA, development of resistive zone in the dipole bus bar splice between Q24 R3 and the neighbouring dipole
 - Electrical arc developed which punctured the helium enclosure




Bus bar splice




Joint components before soldering




Bus bar well reconstituted after soldering





Longitudinal section of the joint, entirely filled with Sn-Ag








Electrical arc between C24 and Q24




M3 line

V lines




The cause (bad splice)




No electrical contact between wedge and U-profile with the bus on at least 1 side of the joint

No bonding at joint with the U-profile and the wedge



The LHC repairs in detail




+ 8 cryogenics!

A78_RB_20091003_203515-235924.data

Close

A78.RB: Normalized Bus Segment Resistance



Rexcess = Rbus - Nsplice * Rsplice show excess?

Every single sc splice were measured in 2009

1				
2				
3				
4	DCBB.11L8.R	3	-1.29E-9	7.64E-10
5	DCBB.A12L8.R	4	-8.41E-10	9.50E-10
6	DCBB.B12L8.R	2	-1.04E-9	5.10E-10
7	DCBB.13L8.R	3	-6.11E-10	3.60E-10
8	DCBB.A14L8.R	3	-4.81E-10	2.54E-10
9	DCRR.B14L8.R	2	-6.26E-10	5.51E-10

histogram count

gaussian fit

sum 424


mean 309pOhm

stdDev 147pOhm

gaussianCenter 293pOhm

gaussianStdDev 109pOhm


weight?






The near future:

Decided Scenario 2010-2011



- Run at 3.5 TeV/beam up to a integrated luminosity of around 1fb^{-1} .
- Then consolidate the whole machine for 7TeV/beam (during a shutdown in 2012)
- From 2013 onwards LHC will be capable of maximum energies and luminosities





Why are we limiting the beam energy to 3.5TeV in 2010-2011?

All the work we have done since November 2008 makes us certain that a **repeat** of September 19 can NEVER happen.


The offending connector in this incident had an estimated resistance of 220n Ω . We have measured all 10,000 inter-magnet connectors and the maximum resistance we have seen is 2.8n Ω .

BUT in April 2009, we have uncovered a different possible failure scenario which could under certain circumstances produce again a thermal runaway in the magnet interconnects:


The lack of continuity in the stabilizer



Defective interconnection-bus bar transition
 γ -ray picture (left) and scheme (right)




A joint between bus bar can quench even if the splice is well done.
 When a magnet quenches, the warm helium wave makes the SS cable in the joint to quench in about 10-20 s. Since the decay time of the current is 104 s in the bus bar (and so in the joint), cable will become resistive and the stabilizing copper is there just to avoid overheating by diluting the current density.
 If the current has to pass through the SC cable only, above a certain length it burns. We know we have this situation: then we limit the dipole current to 6 kA (4.2 T \longrightarrow 3.5 TeV/beam)




First Collisions at 7TeV cm

March 30, 2010




ATLAS IP Separation

$H = 4.173 \text{ mm} : V = 0.035 \text{ mm}$




CMS IP Separation


$H = 0.130 \text{ mm} : V = 3.925 \text{ mm}$



ATLAS Coll Rate Evol



CMS Coll Rate Evol





30/3/2010

11:15 injected again
12:38 : At 3.5 TeV

OP Vistars - Mozilla Firefox

http://op-webtools.web.cern.ch/op-webtools/vistar/vistars.php?usr=LHC1

OP Vistars

LHC Page1 Fill: 1005 E: 3500 GeV 30-03-2010 13:24:16

PROTON PHYSICS: STABLE BEAMS


Energy:	3500 GeV	I(B1):	1.88e+10	I(B2):	1.68e+10
----------------	----------	---------------	----------	---------------	----------

FBCT Intensity Updated: 13:24:16

Time

<p>Comments 30-03-2010 13:22:57 :</p> <p style="text-align: center;">Stable beams!</p>	<p>BIS status and SMP flags</p> <table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>B1</th> <th>B2</th> </tr> </thead> <tbody> <tr> <td>Link Status of Beam Permits</td> <td style="background-color: green; color: white;">true</td> <td style="background-color: green; color: white;">true</td> </tr> <tr> <td>Global Beam Permit</td> <td style="background-color: green; color: white;">true</td> <td style="background-color: green; color: white;">true</td> </tr> <tr> <td>Setup Beam</td> <td style="background-color: green; color: white;">true</td> <td style="background-color: green; color: white;">true</td> </tr> <tr> <td>Beam Presence</td> <td style="background-color: green; color: white;">true</td> <td style="background-color: green; color: white;">true</td> </tr> <tr> <td>Moveable Devices Allowed In</td> <td style="background-color: green; color: white;">true</td> <td style="background-color: green; color: white;">true</td> </tr> <tr> <td>Stable Beams</td> <td style="background-color: green; color: white;">true</td> <td style="background-color: green; color: white;">true</td> </tr> </tbody> </table>		B1	B2	Link Status of Beam Permits	true	true	Global Beam Permit	true	true	Setup Beam	true	true	Beam Presence	true	true	Moveable Devices Allowed In	true	true	Stable Beams	true	true
	B1	B2																				
Link Status of Beam Permits	true	true																				
Global Beam Permit	true	true																				
Setup Beam	true	true																				
Beam Presence	true	true																				
Moveable Devices Allowed In	true	true																				
Stable Beams	true	true																				

LHC Operation in CCC : 77600, 70480 PM Status B1 ENABLED PM Status B2 ENABLED



Soon after the first Collisions





A very good 48 hour period!

06-Apr-2010 17:27:13 Fill #: 1023 Energy: 297.4 GeV I(B1): 1.55e+08 I(B2): 7.01e+07

	ATLAS	ALICE	CMS	LHCb
Experiment Status	STANDBY	NOT READY	STANDBY	STANDBY
Instantaneous Luminosity	0.000e+00	0.000e+00	0.000e+00	8.989e-04
BRAN Count Rate	3.229e-07	4.059e-32	2.086e-11	1.635e-32
BKGD 1	0.002	0.014	0.002	0.131
BKGD 2	0.000	0.000	0.002	0.002
BKGD 3	0.000	0.005	0.003	0.037



LHCf **STANDBY** Count(Hz): 0.000 | LHCb VELO Position **OUT** Gap: 58.0 mm | TOTEM: **CALIBRATION**



Performance over the last 12 Hrs



IP1&5 lumi vs squeeze

- Raw (online) lumi plots on 10 apr 2010, during the squeeze to 2m in IP1 and IP5
- Factor gained (raw numbers):
 - ~4.5 in Pt5 (after min scan)
 - ~4 in Pt1
- Not corrected for lumi decay over the ~5h of squeeze and mini scans






LHC Design Bunch Intensity: Thursday 15.4.2010

- Higher intensity
 - Over-injection working well
 - Over-injected $1.1E11$, with collimators at nominal 4.5 sigma settings.
 - Emittance at $1E11$: 2.5 μm H, 2,3 μm V.

Qualification: Off-momentum collimation



Loss map for off-momentum error. All OK. See expected low leakage to experimental IR's. OK for stable beams from coll.




Transverse Damper: Damping Beam Excitations

Crucial device to keep emittance growth under control!

Wolfgang Hoefle et al





Transverse Damper will stabilize against the Hump



Collisions with design current at 450GeV


	ATLAS	ALICE	CMS	LHCb
Experiment Status	PHYSICS	PHYSICS	PHYSICS	PHYSICS
Instantaneous Luminosity	4.080e-03	2.376e-03	3.276e-03	2.314e-03
BRAN Count Rate	0.000e+00	0.000e+00	5.000e+00	1.000e+00
BKGD 1	0.015	0.013	0.010	0.122
BKGD 2	0.000	5.000	0.774	0.850
BKGD 3	0.000	0.005	0.003	0.047

LHCf **PHYSICS** Count(Hz): 0.000 | LHCb VELO Position **IN** Gap: 20.0 mm | TOTEM: **STANDBY**






Pushing Number of $2e10$ Bunches




$2 \times 2e10 \rightarrow 4 \times 2e10$

$6 \times 2e10$ per beam




← 48 hours →

Allowed doubling the integrated luminosity for 2010 within 48 hours!





13 bunches: 3×10^{29} !!



VLC media player

File View Settings Audio Video Navigation Help

25-May-2010 03:32:50 Fill #: 1122 Energy: 3500 GeV I(B1): 3.22e+11 I(B2): 3.29e+11

	ATLAS	ALICE	CMS	LHCb
Experiment Status	PHYSICS	PHYSICS	PHYSICS	PHYSICS
Instantaneous Lumi (ub.s) ⁻¹	0.205	0.207	0.221	0.209
BRAN Count Rate (Hz)	2.727e+03	1.680e+03	3.979e+03	5.139e+03
BKGD 1	0.009	0.004	0.804	0.160
BKGD 2	0.000	420.420	87.974	4.457
BKGD 3	0.000	0.002	0.003	0.051

LHCf **PHYSICS** Count(Hz): 84.900 LHCb VELO Position **IN** Gap: 0.0 mm TOTEM: **STANDBY**

Performance over the last 12 Hrs Updated: 03:32:50


Background 1 Updated: 03:32:50

Background 2 Updated: 03:32:50

0:00:00 / 0:00:00 x1.00 "LHC Operation"



Getting to Stable beams at 1.1×10^{11} .






Instabilities in Collision at 3.5TeV/beam

- longitudinal emittance control
 - In the SPS
 - During the ramp in the LHC
- Transverse damper working
- Collimators set up
- Injection set up for new high intensity
- Beam dump set up for higher intensity

- Started physics data taking under these conditions on Saturday 26th June


	ATLAS	ALICE	CMS	LHCb
Experiment Status	STANDBY	CALIBRATION	STANDBY	STANDBY
Instantaneous Lumi (ub.s) ⁻¹	0.000	0.000	0.000	0.000
BRAN Count Rate (Hz)	2.000e+00	0.000e+00	1.000e+00	4.000e+01
BKGD 1	0.002	0.004	0.002	0.122
BKGD 2	0.000	0.000	0.004	1.727
BKGD 3	0.000	0.001	0.003	0.037

LHCf STANDBY Count(Hz): 0.000 | LHCb VELO Position OUT Gap: 58.0 mm | TOTEM: STANDBY



Ramps for Operations set up for 10¹¹ protons/bunch

26th June: 5×10^{29} with 3 bunches/beam; $10^{11}/b$



VLC media player

File View Settings Audio Video Navigation Help

26-Jun-2010 20:22:09 Fill #: 1182 Energy: 3500 GeV I(B1): 2.73e+11 I(B2): 2.84e+11

	ATLAS	ALICE	CMS	LHCb
Experiment Status	PHYSICS	PHYSICS	PHYSICS	PHYSICS
Instantaneous Lumi (ub.s) ⁻¹	0.500	0.275	0.516	0.444
BRAN Count Rate (Hz)	5.395e+03	3.675e+03	7.550e+03	8.960e+03
BKGD 1	0.022	0.014	1.178	0.131
BKGD 2	3.000	755.420	0.002	1.238
BKGD 3	0.000	0.006	0.003	0.054

LHCf **PHYSICS** Count(Hz): 565.500 | LHCb VELO Position **OFF** Gap: 58.0 mm | TOTEM: **CALIBRATION**


Performance over the last 12 Hrs Updated: 20:22:09

Background 1 Updated: 20:22:09

Background 2 Updated: 20:22:09

0:00:00 / 0:00: x1.00 "LHC Operation"

2nd July: Colliding 6 bunches per beam; 10¹¹/b



VLC media player

File View Settings Audio Video Navigation Help

02-Jul-2010 05:44:10 Fill #: 1190 Energy: 3500 GeV I(B1): 5.94e+11 I(B2): 6.14e+11

	ATLAS	ALICE	CMS	LHCb
Experiment Status	PHYSICS	PHYSICS	PHYSICS	PHYSICS
Instantaneous Lumi (ub.s) ⁻¹	0.631	0.000	0.642	0.173
BRAN Count Rate (Hz)	6.729e+03	0.000e+00	9.863e+03	3.740e+03
BKGD 1	0.080	0.019	1.394	0.141
BKGD 2	2.000	0.001	0.002	0.002
BKGD 3	0.000	0.006	0.003	0.048

LHCf **REMOVED** Count(Hz): 0.000 LHCb VELO Position **OFF** Gap: 58.0 mm TOTEM: **STANDBY**

Performance over the last 12 Hrs Updated: 05:44:10


Background 1 Updated: 05:44:10

Background 2 Updated: 05:44:10

0:00:00 / 0:00: x1.00 "LHC Operation"



6 bunches/beam New Record Lumi > 1e30 cm⁻²s⁻¹




02-Jul-2010 17:36:21 Fill #: 1192 Energy: 3500 GeV I(B1): 6.65e+11 I(B2): 6.70e+11

	ATLAS	ALICE	CMS	LHCb
Experiment Status	PHYSICS	PHYSICS	PHYSICS	PHYSICS
Instantaneous Lumi (ub.s) ⁻¹	1.054	0.004	1.172	1.047
BRAN Count Rate (Hz)	1.098e+04	3.100e+01	1.657e+04	2.124e+04
BKGD 1	0.028	0.016	2.416	0.169
BKGD 2	0.000	0.008	0.002	1.974
BKGD 3	0.000	0.005	0.003	0.060

LHCf **MOVING** Count(Hz): 0.114 LHCb VELO Position **OUT** Gap: 58.0 mm TOTEM: **STANDBY**

Performance over the last 12 Hrs

Updated: 17:36:20



Emittances before ramp :

- B1 H: 2.5
- B1 V: 2.5
- B2 H: 2.5
- B2 V: 3.0 (measure not so good)


Emittances meas during the ramp

- B1 H: 4.2
- B1 V: 5.1
- B2 H: 2.3
- B2 V: 2.9




LHC status

Beam Lifetime







LHC-FBCT Average Lifetime

FBCT Average Beam Lifetime in h






Better but not perfect stability...





2010/07/14 08.21

LHC 2010 RUN (3.5 TeV/beam)




* ALICE: low pile-up since 01.07.2010

The same vs fill number in log graph



2010/07/14 08.22


LHC 2010 RUN (3.5 TeV/beam)



* ALICE: low pile-up since 01.07.2010




Summary of Milestones thus far



- **30 March: first collisions at 3.5TeV/beam**
- **19 April: order of magnitude increase in luminosity**
 - doubling the number of particles/bunch
 - β^* from 11 to 2m (4b/beam) $L \sim 2 \times 10^{28}$.
 - Beam lifetimes of ~ 1000 hours
- **22 May another order of magnitude:**
 - 13 bunches in each beam ($L \sim 3 \times 10^{29}$)
- **26 May: Design intensity bunches were brought into collision at 3.5TeV/beam.**
- **2nd July peak luminosity of $10^{30} \text{cm}^{-2} \text{s}^{-1}$.**
- **Half July: $1.4 \times 10^{30} \text{cm}^{-2} \text{s}^{-1}$ consolidated, aiming at more**
- **By August : bunch train**




Presently



- **From experience so far**
 - No fundamental issue for $1e30$ luminosity
 - Further equalize beam parameters (emittance, intensity, ...) while delivering luminosity. Try to get nominal beam and bunch parameters, including variations.
 - As stability is improved, push up again on luminosity
- **In addition:**
 - Cross calibrate emittance measurement devices.
 - Push transverse damper into full operation in collision, however, possibly needs noise reduction.


Aim is for 10^{32} before the end of 2010 which is needed for an integrated luminosity of **1fb-1 before end of 2011**

At 7 Tev c.o.m. energy



10³² how far we are ?

1e32 !!




(modulo some possible luminometers down time...)

Fills 1005-1199


2010/07/07 08.08

LHC 2010 RUN (3.5 TeV/beam)



2010/07/07 08.08


LHC 2010 RUN (3.5 TeV/beam)



~70 days





Medium future : 2012-13 shutdown





- **Splice consolidation for nominal energy 13-14 TeV c.o.m.**
 - All sectors to be warmed up
 - All Interconnects to be opened (about 2000), and 5000 helium enclosure - pipes with flanges and bellow - cut and opened
 - All 10,000 joints inspected, some 15% expected to be repaired and **ALL to be consolidated with a copper shunt**
 - Some 5 magnets to be replaced for electric or vacuum defects and 10-15 for n.c. internal (inside magnets) splice.
- **Completion of collimation system for nominal luminosity**
 - (we think we will be limited at 2-20% of nominal luminosity by lack of complete collimation)
 - This requires to remove to surface 24 main magnets (+ 4 cryostats) and to reinstall in displaced position in order to fit:
 - **NEW 4 cold-warm-cold transitions to place 4 collimators in the DS zone of P3** (in addition to six more normal collimators still missing)

Sketch of the copper shunt





Sketch of the restraining box







A possible schedule for the next decade






A look to a possible – possible!!! – lumi evolution





Far Future - High Luminosity LHC : aim at $5 \cdot 10^{34}$ with leveling



■ New Hardware


- 13 T magnets, 16 high grad low beta quadrupoles for ATLAS & CMS and 4 large aperture dipoles
- New IR magnet layout with also new cryo-plants
- New SC crab cavities to rotate the beam and make effective the gain of the low beta quads
- New magnets in the Matching sections with larger apertures
- New Sc links to remove Power Supply on surface (R2E problem)
- Further collimation system in the DS of P7, IP2 (IP1 and IP5?) requiring special 11 T LHC like dipoles
- New collimation system and absorber in the IR to protect magnets.

■ What is the time scale ?

- The Study and R&D takes 5 years
- In 2013-14 we are ready for a decision, then 5 year to built and test
- Installation from 2020... some 1500-2000 fb⁻¹ by 2030...




Are we ready with this new technology? Almost...




US – LARP (DOE program) is developing Nb₃Sn SC magnets
LQS is a 3.6 m coil length quadrupole with **90 mm aperture**. Its goal is 200 T/m, as LHC @ 70 mm and 1.9 K!

LQS01b Quench History








Very Far Future - High Energy LHC : aim at 28-33 TeV c.o.m.




■ New Hardware

- 17-20 T main dipole magnets!
- Synchrotron radiation also a big issue
- But it looks possible...
- Sketch of a 20 T dual dipole with 40 mm bore with Nb-Ti (LHC), Nb₃Sn (HL-LHC) and HTS.
- Working group lead by S. Meyers is – slowing – taking momentum
- Taking profit from HL-LHC R&D



■ What is the time scale ?

- The Study, R&D, industrialization will take 10 years
- Construction further 10 years
- Installation from 2030... or later



- **LHC is finally there !**
 - 1 fb⁻¹ @ 7 TeV c.o.m. by 2011
 - 14 TeV and 50-100 fb⁻¹ by 2016,
 - 200-400 fb⁻¹ by 2020.
- **HL-LHC**
 - aiming @ 5 10³⁴ cm⁻² s⁻¹ average, 1500-2000 fb⁻¹ by 2030
 - decision in 2014 for installation in 2020
 - cost : 500 Millions
- **HE-LHC**
 - Aim at 28-33 TeV c.o.m by 2030...
 - Cost : 5000 Millions + ...
 - I don't know if physics requires such accelerator...
 - **If we can afford a linear collider, we can certainly afford HE-LHC !**

