Neutrino Non-Standard Interactions: Complementarity Between LHC and Oscillation Experiments

K.S. Babu, ^{1,*} Dorival Gonçalves, ^{1,†} Sudip Jana, ^{2,‡} and Pedro A. N. Machado ^{3,§}
¹Department of Physics, Oklahoma State University, Stillwater, OK, 74078, USA
²Max-Planck-Institut für Kernphysik, Saupfercheckweg 1, 69117 Heidelberg, Germany
³Fermi National Accelerator Laboratory, Batavia, IL, 60510, USA

We explore the complementarity between LHC searches and neutrino experiments in probing neutrino non-standard interactions. Our study spans the theoretical frameworks of effective field theory, simplified model and an illustrative UV completion, highlighting the synergies and distinctive features in all cases. We show that besides constraining the allowed NSI parameter space, the LHC data can break important degeneracies present in oscillation experiments such as DUNE, while the latter play an important role in probing light and weakly coupled physics undetectable at the LHC.

I. Introduction — In spite of its vast success, the Standard Model (SM) does not shed any light on the origin of neutrino masses. Overwhelming experimental evidence has shown that neutrinos of different flavors oscillate among one another, which cannot occur without small neutrino masses. New physics is necessary for generating such masses, and thus the study of neutrinos offers a promising window for physics beyond the Standard Model.

The new physics associated with neutrino masses can lie in a vast range of energy scales: from sub-GeV to the TeV region, even reaching unification scales of order 10¹⁴ GeV. This poses a phenomenological challenge that should be addressed with multiple experiments probing different energy scales, and in combination with suitable theoretical frameworks. For instance, neutrino Non-Standard Interactions (NSI) with matter can change the neutrino oscillation probabilities [1], where the momentum transfer is negligible, $q^2 \rightarrow 0$ (for a summary of current status of NSI see Ref. [2]). Therefore, the impact of new physics in oscillation experiments is well described by Effective Field Theory (EFT). In contrast, at high energy colliders, the momentum transfer can be sizable, $q^2 \sim \text{TeV}^2$, possibly leading to direct production of new states, where the consistency of EFT may no longer be guaran-

$$\mathcal{L}_{\text{NSI}} = -2\sqrt{2}G_F \epsilon_{\alpha\beta}^{fY} \left(\bar{\nu}^{\alpha} \gamma_{\mu} \nu^{\beta}\right) \left(\bar{f} \gamma^{\mu} P_Y f\right) , (1)$$

teed [3–8]. Here, a well suited framework should

at least include the new degrees of freedom, as in

simplified models, or may display an even richer phenomenology, as in a UV complete scenario.

complementarity of neutrino experiments such

as DUNE and collider searches in probing NSIs,

across this multitude of frameworks: from the

EFT to simplified models, and an illustrative UV

completion. In Sec. II we define EFT and sim-

plified scenarios and use them to evaluate the

LHC sensitivity to NSIs, in Sec. III we discuss

the complementarity between LHC and oscilla-

tion physics, in Sec. IV we present an illustrative

II. From EFTs to Simplified Models – Neu-

trino oscillation probabilities are modified in a

medium in the presence of NSI, which are gen-

UV completion, and in Sec. V we conclude.

The purpose of this paper is to highlight the

where $\epsilon_{\alpha\beta}^{fY}$ defines the strength of the $\nu-f$ interaction, Y=L or R, P_L (P_R) is the left (right) chiral projector, $\alpha,\beta\in\{e,\mu,\tau\}$, and $f=\{u,d,e\}$.

These new physics contributions can arise from higher dimensional operators that are invariant under the SM gauge symmetry. The dominant effects are expected to come from dimension six operators such as

$$\frac{1}{\Lambda^2} \left(\overline{L}_{\alpha} \gamma_{\mu} L_{\beta} \right) \left(\overline{q} \gamma^{\mu} P_X q \right) , \qquad (2)$$

erally parametrized in the EFT framework as: $\frac{F_{1}}{2} = \frac{fY_{1}}{2} \left(\frac{1}{2} + \frac{1}{2} +$

^{*} E-mail:babu@okstate.edu

[†] E-mail:dorival@okstate.edu

[‡] E-mail:sudip.jana@mpi-hd.mpg.de

[§] E-mail:pmachado@fnal.gov

where L is the lepton doublet and X = L/R. It follows that $\epsilon_{\alpha\beta} = -1/(2\sqrt{2}G_F\Lambda^2)$. One would expect prohibitively strong constrains on such operators from charged lepton flavor violation processes [9]. However, flavor diagonal operators can avoid these constraints and lead to observable NSI [10].

Dimension 8 operators of the type

$$\frac{1}{\Lambda^4} \left(\overline{HL}_{\alpha} \gamma_{\mu} H L_{\beta} \right) \left(\bar{q} \gamma^{\mu} P_X q \right) , \qquad (3)$$

where H is the Higgs doublet [4], do not directly suffer from charged lepton flavor violation constraints, although there are other limits arising from non-unitarity of the PMNS matrix, oblique electroweak corrections, etc. [11]. If the mass of the mediator inducing Eq. (1) is below the electroweak scale, charged lepton flavor violation constraints may even be absent [12, 13].

While for oscillation experiments, we can safely take an agnostic approach to the origin the NSI operators and apply Eq. (1), at the energy scales and couplings probed at the LHC, the validity of the EFT approach is no longer This discussion is similar to reguaranteed. cent considerations about the interplay between dark matter (DM) searches at the LHC and low energy direct detection experiments [14–17]. Namely, while bounds from DM direct detection experiments on new physics can be interpreted in the EFT regime through operators like $(\bar{\chi}\gamma_{\mu}\chi)(\bar{q}\gamma^{\mu}q)/\Lambda^2$, the same does not hold true at the LHC, where the momentum transfers can go beyond the validity of EFT. Simplified models, in which the force mediator is dealt with explicitly, have been shown to be more appropriate for collider studies. Adopting a simplified model approach, we parametrize the NSI as

$$\mathcal{L}_{\mathrm{NSI}}^{\mathrm{Simp}} = \left(g_{\nu}^{\alpha\beta} \bar{\nu}_{\alpha} \gamma^{\mu} P_{L} \nu_{\beta} + g_{q}^{Y} \bar{q} \gamma^{\mu} P_{Y} q \right) Z_{\mu}', \quad (4)$$

where Z'_{μ} denotes the new force carrier with arbitrary mass $M_{Z'}$ [3, 5]

Manifestations of dark matter and nonstandard neutrino interactions at colliders would look quite similar, both involving large amount of missing transverse energy. A powerful probe of these interactions is the study of mono-jet signatures, in which QCD initial state radiation




Figure 1. Constraints on neutrino non-standard interactions from LHC data and neutrino experiments [24] as a function of the mediator mass $M_{Z'}$, assuming $\epsilon_{\alpha\beta} \equiv \epsilon^u_{\alpha\beta} = \epsilon^d_{\alpha\beta}$. Note that LHC constraints are independent of neutrino flavor. We assumed $\Gamma_{Z'}/M_{Z'}=0.1$ here.

leads to quark and gluon emission, $pp \to j + E_T$ with $j = q, \bar{q}, g$. In this context, it has been shown that constraints from LHC 8 TeV data are more stringent for $M_{Z'} \gtrsim 100$ GeV with the sensitivity reaching $\epsilon \lesssim 10^{-2}$ [5, 6].

To estimate the current and high-luminosity LHC sensitivity to NSIs, we will recast the recent jets plus missing energy searches from AT-LAS [18] into the simplified model of Eq. (4). The limit $M_{Z'} \gg \sqrt{s}$ can be identified as the EFT in Eq. (1). For our analysis, we generate the signal sample $pp \to \nu \bar{\nu} j$ with MAD-GRAPH5AMC@NLO [19, 20], simulating the hadronization and underlying event effects with PYTHIAS [21]. Detector effects are simulated with the DELPHES3 package [22].

Following the recent 13 TeV ATLAS monojet study [18], we define jets with the anti- k_t jet algorithm and radius parameter R=0.4, $p_{Tj}>30$ GeV and $|\eta|<2.8$ via FASTJET [23]. Events with identified electrons with $p_T>20$ GeV or muons $p_T>10$ GeV in the final state are vetoed. To suppress the Z+jets and W+jets backgrounds, the events are selected with $E_T>250$ GeV recoiling against a leading jet with $p_{Tj1}>250$ GeV, $|\eta_{j1}|<2.4$, and azimuthal separation $\Delta\phi(j_1,\vec{p}_{T,miss})>0.4$. Events with more than four jets are vetoed.

Although flavor diagonal NSIs may interfere

with the SM background $Z(\nu\bar{\nu})$ +jets, we find it to be negligible in the region of interest for the LHC sensitivity. Therefore, the diagonal and non-diagonal NSIs result in equivalent bounds at LHC. Note also that, in fixing the total width, the number of signal events is proportional to $\epsilon^2 \equiv (\sum_{\alpha,\beta} |\epsilon_{\alpha\beta}|^2)$ for both on-shell and off-shell production, and thus we use ϵ to quantify the LHC sensitivity to NSIs. This eases the comparison to neutrino experiments without any further assumptions about the g_{ν} vs. g_q ratio.

For concreteness, we will assume that neutrino NSIs arise in the simplified model (4) as

$$\epsilon_{\alpha\beta}^{u} = \epsilon_{\alpha\beta}^{d} \equiv \epsilon_{\alpha\beta} = \frac{(g_{\nu})_{\alpha\beta}g_{u,d}^{V}}{2\sqrt{2}G_{F}M_{Z'}^{2}},$$
 (5)

where $g_{u,d}^V = g_{u,d}^L + g_{u,d}^R$ is the quark vector current. We shall assume that $g_u^V = g_d^V$ and $g_{u,d}^A = 0$ in presenting most of our numerical results, except in the context of an explicit model where these relations are not realized.

A major limitation of such searches is associated with the overwhelming SM backgrounds, $pp \to Z(\nu\nu)j$ and $pp \to W(\ell\nu)j$, which suffer from large theoretical uncertainties, including higher-order QCD and electroweak corrections. Nevertheless, recently efforts have been made to improve the signal sensitivity in both experimental and theoretical fronts [25]. These include further exploration of background control regions and state-of-the-art Monte Carlo simulations, resulting in suppressed background uncertainties and augmented sensitivity to new physics. These advancements lead to suppressed systematic uncertainties that pave the way to stronger NSI constraints at the high-luminosity LHC.

In Fig. 1, we present the LHC sensitivity to NSIs at 95% CL, estimated for two LHC integrated luminosity scenarios: 36.1 fb^{-1} and 3 ab^{-1} . For the lower luminosity case, AT-LAS [18] provides a limit on the signal events for ten signal regions. They differ by increasing E_T thresholds. We define the NSI constraint by the most sensitive region (black line). For the high-luminosity scenario, we obtain the backgrounds from ATLAS in the same ten E_T thresholds. The NSI sensitivity is obtained from the signal region that maximizes the significance

 $S=N_{\rm s}/\sqrt{N_{\rm b}+(\delta\sigma_{\rm b}.N_{\rm b})^2}$, where $N_{\rm s}$ and $N_{\rm b}$ are the signal and background events, respectively, and $\delta\sigma_{\rm b}$ is the background uncertainty. To evaluate the impact of systematic uncertainties at the high-luminosity LHC, the sensitivities are evaluated in two scenarios: $\delta\sigma_{b}=1\%$ and 3%. The future high-luminosity LHC sensitivity is shown as a blue region, in which the impact of such uncertainties is conveyed as a band. The resulting LHC constraint is maximal for mediators masses of order $M_{Z'}\sim 2$ TeV, reaching $\epsilon\lesssim 2\times 10^{-3}$. Flavor dependent bounds on NSI from neutrino experiments [24] are shown as dashed lines and will be discussed in the following section.

We can identify the EFT regime for the LHC when the mass of the mediator is much above the scale of the process involved. This can clearly be seen in Fig. 1, as the bound on ϵ does not change for mediator masses above ~ 5 TeV. In addition, a robust argument can be made to estimate the validity of this EFT at the LHC. For any fixed ratio $\Gamma_{Z'}/M_{Z'}$, we can write the following inequality

$$|\epsilon| \le \frac{\sqrt{3}\pi}{\sqrt{2}G_F M_{Z'}^2} \frac{\Gamma_{Z'}}{M_{Z'}} \ . \tag{6}$$

This constraint originates from the fact that the total width of the Z' should be larger than the partial widths to $u\bar{u}$, $d\bar{d}$, and $\nu\bar{\nu}$: $\Gamma_{Z'} \geq M_{Z'}/(24\pi)(g_{\nu}^2+6\{(g_u^V)^2+(g_d^V)^2\})$, where we assumed decay to a single neutrino flavor. Considering non-zero axial couplings would make the constraint more stringent. Assuming $g_u^V = g_d^V$ leads to the "inconsistent region" (gray shaded) in Fig. 1. Considering narrower Z' makes the constraint stronger, while broader Z' implies non-perturbativity ($\Gamma_{Z'}$ greater than roughly half $M_{Z'}$). Therefore, traditional EFT analyses at the LHC using four-fermion operators like Eq. (1) will typically not be valid, at least having simple/minimal UV completions in mind.

III. Complementarity between LHC and neutrino experiments — Differently from the LHC, the effects of NSIs in neutrino oscillations strongly depend on the flavor structure of the NSI and the oscillation channel being studied.

In Fig. 1, we show the limits on $|\epsilon_{\alpha\beta}|$ for each flavor combination, derived from the global




Figure 2. Constraints on neutrino non-standard interactions from LHC data, for different mediator masses as labeled, with $\Gamma_{Z'}/M_{Z'}=0.1$, assuming $\epsilon_{\alpha\beta}\equiv\epsilon^u_{\alpha\beta}=\epsilon^d_{\alpha\beta}$. A fit to simulated data for DUNE from Ref . [26] is also included (pink shaded region).

fit [24] using neutrino oscillation and COHER-ENT data, where all other NSI parameters were marginalized over. We have combined the limits on $\epsilon^u_{\alpha\beta}$ and $\epsilon^d_{\alpha\beta}$ at 95% CL in [24] in quadrature, $\sigma_{\alpha\beta} = [(\sigma^u_{\alpha\beta})^{-2} + (\sigma^d_{\alpha\beta})^{-2}]^{-1/2}$. These constraints on NSI parameters span two orders of magnitude, showing the strong dependency on the flavor structure of the NSI.

The flavor dependence of NSIs on neutrino oscillations goes beyond different sensitivities. The effects of different NSIs and/or variations of the standard oscillation parameters can, in some cases, compensate each other and lead to well known degeneracies. Disentangling those is a difficult task at neutrino facilities. In contrast, the mono-jet signal at the LHC, $pp \rightarrow \bar{\nu}_{\alpha}\nu_{\beta}j$, does not distinguish between different choices of (α, β) ; i.e., they all lead to the same observables. Besides constraining the currently allowed NSI parameter space, this feature can be further exploited to break relevant degeneracies.

To make this point manifest, we present two examples of degeneracy breaking in the following. In Fig. 2, we show the 95% CL bounds on $|\epsilon_{ee}|$ vs. $|\epsilon_{e\tau}|$ from Ref. [26], obtained by combining current oscillation and scattering data with future DUNE sensitivity. In Fig. 3, we show the 95% CL bounds on $\epsilon_{e\tau}$ vs. the usual CP violating phase δ for the future DUNE experiment from Ref. [27]. Here, $\nu_{\mu} \rightarrow \nu_{e}$ and $\bar{\nu}_{\mu} \rightarrow \bar{\nu}_{e}$




Figure 3. An example of degeneracy in the $(\epsilon_{e\tau}, \delta)$ plane, where δ is the standard CP violating phase and $\epsilon_{e\tau} \equiv \epsilon^u_{e\tau} = \epsilon^d_{e\tau}$, from future DUNE data taken from Ref. [27] (pink shaded regions are allowed, assuming $\epsilon_{e\tau} = \delta = 0$ as null hypothesis). We overlay the LHC sensitivity to this NSI parameter for several mediator masses, as labeled, assuming $\Gamma_{Z'}/M_{Z'} = 0.1$.

oscillation channels, driven by the smallest mixing parameter, $\sin^2 2\theta_{13}$, are crucial to constrain these parameters. These oscillations are significantly affected by matter effects, and channels like $\nu_{\mu} \to \nu_{\tau}$, $\nu_{e} \to \nu_{\mu}$ are much harder to study due to experimental limitations. The allowed regions from neutrino experiments are shown in pink shaded, while the LHC bound depends on the mediator mass and is depicted as colored lines, as indicated in the figures. It should be noted that, even with the future DUNE experiment, several degeneracies will remain unsolved by oscillation measurements, but could in principle be unravelled by LHC data.

Therefore, several important complementary aspects between LHC and neutrino experiments can already be identified. The LHC sensitivity displays a strong dependence on the mediator mass, but it is free of parameter degeneracies. Neutrino oscillation measurements, on the other hand, exhibit the opposite behavior: significant degeneracies and no mediator mass dependence.

On top of that, there is another complementary aspect that cannot be seen from the figures presented so far. The matter potential induced when neutrinos travel through a medium is not affected by a diagonal, universal contribution (as

this just induces an overall phase shift on the neutrino state). On the other hand, LHC data is sensitive to each and all NSI parameters independently. Note also that neutrino oscillations are not sensitive to axial interactions, while LHC data is sensitive to both vector and axial new physics contributions. All these features show the synergies between oscillation measurements and collider data on probing new physics in the neutrino sector.

IV. Towards a UV complete scenario Any UV complete model of neutrino NSI is expected to provide a more extensive phenomenology, especially since neutrinos are in the same $SU(2)_L$ doublet as charged leptons. This further enhances the synergies between LHC and oscillation experiment, as we shall demonstrate in an illustrative UV completion. We show in Fig. 4 the constraints on the UV complete model of Ref. [12] (see Ref. [28] for other constructions with leptonic signals). In this UV completion the B-L number is gauged, but only for the third family. This leads to a new gauge boson that couples more strongly with the third family fermions and results in nonzero $\epsilon_{\tau\tau}$. In Ref. [12] the entire model was specified, and an extensive list of constraints were derived from low energy observables such as neutrino oscillation, D-Dmixing, Υ and B decays, atomic parity violation, and others.

Assuming $\tan \beta = 0.5$ (see Ref. [12]), we compare these constraints (black line) with a dedicated $bb\tau\tau$ search [29] (red line), electroweak precision T parameter [30] (green solid and dotted line) and the high-luminosity LHC jets plus missing energy constraint of Sec. II (blue line). The latter displays a distinctive profile due to enhanced light flavors initial state contributions for $M_{Z'} \sim M_Z$ and b-initiated at $M_{Z'} \gg M_Z$. If $M_Z < M_{Z'}$, the contribution to the T parameter can in principle be compensated by those stemming from the scalar sector, making this constraint model dependent (indicated by the dotted green line). Finally, we also show the region in which the theory becomes non-perturbative, corresponding to the new gauge coupling being larger than 2.0.

Low energy constraints, dedicated LHC




Figure 4. Sensitivities to a specific UV complete model realization of non-standard interactions where the B-L number of the third family is gauged [12]. This includes current low energy observables (black), electroweak T parameter (green solid and dotted, see text), future high-luminosity LHC searches for $bb\tau\tau$ final states (red, adapted from Ref. [29]), and LHC mono-jet searches (blue).

searches, and missing energy signatures provide strong constraints for different masses of the mediator. For masses below about 10 GeV, low energy observables tend to dominate. In the intermediate regime 10-100 GeV, dedicated searches for visible signatures at the LHC become more relevant. Finally, from 0.1-1 TeV LHC mono-jet searches and electroweak precision observables (up to the T parameter model dependence) play the leading role. This makes manifest the complementarities among collider data, oscillation measurements, and other low energy observables.

V. Conclusion — We have explored the complementarity between neutrino experiments and LHC searches in probing neutrino non-standard interactions. Our analysis covers the full span of theory frameworks: effective field theories, simplified models, and an illustrative UV completion. We have shown that the present and highluminosity LHC sensitivities to NSIs display relevant synergies to oscillation results. Namely, i) the breakdown of degeneracies among NSI and oscillation parameters, and ii) sensitivity to new phenomenological signatures at the LHC. As a by-product of our analysis, we have shown that the use of EFT at the LHC in estimating sensi-

tivity to NSIs is not generally theoretically consistent.

ACKNOWLEDGMENTS

The work of KB and SJ was supported in part by US Department of Energy Grant Number DE-SC 0016013 and by the Neutrino Theory Network Program Grant No. DE-AC02-

07CHI11359. KB, DG and SJ thank the Fermilab theory group for warm hospitality during the completion of this work. KB is supported in part by a Fermilab Distinguished Scholar program. Fermilab is operated by the Fermi Research Alliance, LLC under contract No. DE-AC02-07CH11359 with the United States Department of Energy.

- L. Wolfenstein, "Neutrino Oscillations in Matter," *Phys. Rev.* **D17** (1978) 2369–2374.
 [,294(1977)].
- [2] P. S. Bhupal Dev et al., "Neutrino Non-Standard Interactions: A Status Report," arXiv:1907.00991 [hep-ph]. [SciPost Phys. Proc.2,001(2019)].
- [3] S. Davidson and V. Sanz, "Non-Standard Neutrino Interactions at Colliders," *Phys. Rev.* D84 (2011) 113011, arXiv:1108.5320 [hep-ph].
- [4] Z. Berezhiani and A. Rossi, "Limits on the nonstandard interactions of neutrinos from e+ e- colliders," *Phys. Lett.* **B535** (2002) 207–218, arXiv:hep-ph/0111137 [hep-ph].
- [5] A. Friedland, M. L. Graesser, I. M. Shoemaker, and L. Vecchi, "Probing Nonstandard Standard Model Backgrounds with LHC Monojets," *Phys. Lett.* B714 (2012) 267–275, arXiv:1111.5331 [hep-ph].
- [6] D. Buarque Franzosi, M. T. Frandsen, and I. M. Shoemaker, "New or ν missing energy: Discriminating dark matter from neutrino interactions at the LHC," *Phys. Rev.* D93 no. 9, (2016) 095001, arXiv:1507.07574 [hep-ph].
- [7] D. Choudhury, K. Ghosh, and S. Niyogi, "Probing nonstandard neutrino interactions at the LHC Run II," *Phys. Lett.* B784 (2018) 248–254.
- [8] I. Bischer and W. Rodejohann, "General neutrino interactions from an effective field theory perspective," *Nucl. Phys.* B947 (2019) 114746, arXiv:1905.08699 [hep-ph].
- [9] S. Bergmann and Y. Grossman, "Can lepton flavor violating interactions explain the LSND results?," *Phys. Rev.* D59 (1999) 093005, arXiv:hep-ph/9809524 [hep-ph].
- [10] K. S. Babu, P. S. B. Dev, S. Jana, and A. Thapa, "Non-Standard Interactions in Radiative Neutrino Mass Models," *JHEP* 03

- (2020) 006, arXiv:1907.09498 [hep-ph].
- [11] M. B. Gavela, D. Hernandez, T. Ota, and W. Winter, "Large gauge invariant non-standard neutrino interactions," *Phys. Rev.* D79 (2009) 013007, arXiv:0809.3451 [hep-ph].
- [12] K. S. Babu, A. Friedland, P. A. N. Machado, and I. Mocioiu, "Flavor Gauge Models Below the Fermi Scale," *JHEP* 12 (2017) 096, arXiv:1705.01822 [hep-ph].
- [13] Y. Farzan and I. M. Shoemaker, "Lepton Flavor Violating Non-Standard Interactions via Light Mediators," *JHEP* 07 (2016) 033, arXiv:1512.09147 [hep-ph].
- [14] G. Busoni, A. De Simone, E. Morgante, and A. Riotto, "On the Validity of the Effective Field Theory for Dark Matter Searches at the LHC," *Phys. Lett.* B728 (2014) 412–421, arXiv:1307.2253 [hep-ph].
- [15] O. Buchmueller, M. J. Dolan, and C. McCabe, "Beyond Effective Field Theory for Dark Matter Searches at the LHC," JHEP 01 (2014) 025, arXiv:1308.6799 [hep-ph].
- [16] D. Goncalves, P. A. N. Machado, and J. M. No, "Simplified Models for Dark Matter Face their Consistent Completions," *Phys. Rev.* D95 no. 5, (2017) 055027, arXiv:1611.04593 [hep-ph].
- [17] N. F. Bell, G. Busoni, and I. W. Sanderson, "Self-consistent Dark Matter Simplified Models with an s-channel scalar mediator," *JCAP* 1703 (2017) 015, arXiv:1612.03475 [hep-ph].
- [18] ATLAS Collaboration, M. Aaboud *et al.*, "Search for dark matter and other new phenomena in events with an energetic jet and large missing transverse momentum using the ATLAS detector," *JHEP* **01** (2018) 126, arXiv:1711.03301 [hep-ex].
- [19] J. Alwall, M. Herquet, F. Maltoni,O. Mattelaer, and T. Stelzer, "MadGraph 5 :

- Going Beyond," *JHEP* **06** (2011) 128, arXiv:1106.0522 [hep-ph].
- [20] J. Alwall, R. Frederix, S. Frixione, V. Hirschi, F. Maltoni, O. Mattelaer, H. S. Shao, T. Stelzer, P. Torrielli, and M. Zaro, "The automated computation of tree-level and next-to-leading order differential cross sections, and their matching to parton shower simulations," *JHEP* 07 (2014) 079, arXiv:1405.0301 [hep-ph].
- [21] T. Sjostrand, S. Mrenna, and P. Z. Skands, "A Brief Introduction to PYTHIA 8.1," *Comput. Phys. Commun.* 178 (2008) 852–867, arXiv:0710.3820 [hep-ph].
- [22] DELPHES 3 Collaboration, J. de Favereau, C. Delaere, P. Demin, A. Giammanco, V. Lemaître, A. Mertens, and M. Selvaggi, "DELPHES 3, A modular framework for fast simulation of a generic collider experiment," JHEP 02 (2014) 057, arXiv:1307.6346 [hep-ex].
- [23] M. Cacciari, G. P. Salam, and G. Soyez, "FastJet User Manual," *Eur. Phys. J.* C72 (2012) 1896, arXiv:1111.6097 [hep-ph].
- [24] P. Coloma, I. Esteban, M. C. Gonzalez-Garcia, and M. Maltoni, "Improved global fit to Non-Standard neutrino Interactions using

- COHERENT energy and timing data," arXiv:1911.09109 [hep-ph].
- [25] J. M. Lindert et al., "Precise predictions for V+ jets dark matter backgrounds," Eur. Phys. J. C77 no. 12, (2017) 829, arXiv:1705.04664 [hep-ph].
- [26] P. Coloma and T. Schwetz, "Generalized mass ordering degeneracy in neutrino oscillation experiments," *Phys. Rev.* D94 no. 5, (2016) 055005, arXiv:1604.05772 [hep-ph]. [Erratum: Phys. Rev.D95,no.7,079903(2017)].
- [27] J. Liao, D. Marfatia, and K. Whisnant, "Degeneracies in long-baseline neutrino experiments from nonstandard interactions," *Phys. Rev.* **D93** no. 9, (2016) 093016, arXiv:1601.00927 [hep-ph].
- [28] T. Han, J. Liao, H. Liu, and D. Marfatia, "Nonstandard neutrino interactions at COHERENT, DUNE, T2HK and LHC," *JHEP* 11 (2019) 028, arXiv:1910.03272 [hep-ph].
- [29] F. Elahi and A. Martin, "LHC constraints on a $(B-L)_3$ gauge boson," *Phys. Rev.* **D100** no. 3, (2019) 035016, arXiv:1905.10106 [hep-ph].
- [30] Particle Data Group Collaboration,
 M. Tanabashi et al., "Review of Particle Physics," Phys. Rev. D98 no. 3, (2018) 030001.