

FERMILAB-SLIDES-20-118-TD

Lessons learned from the prototypes of the MQXFA Low Beta Quadrupoles for HL-LHC and plans for production in the US

Giorgio Ambrosio (Fermilab), and the MQXFA Team



This manuscript has been authored by Fermi Research Alliance, LLC under Contract No. DE-AC02-07CH11359 with the U.S. Department of Energy, Office of Science, Office of High Energy Physics.

Acknowledgement

US HL-LHC Accelerator Upgrade Project (AUP)

- BNL: K. Amm, M. Anerella, A. Ben Yahia, H. Hocker, P. Joshi, J. Muratore, J. Schmalzle, H. Song, P. Wanderer
- FNAL: G. Ambrosio, G. Apollinari, M. Baldini, J. Blowers, R. Bossert, R. Carcagno, G. Chlachidze, J. DiMarco, S. Feher, S. Krave, V. Lombardo, C. Narug, A. Nobrega, V. Marinozzi, C. Orozco, T. Page M. Parker, S. Stoynev, T. Strauss, M. Turenne, D. Turrioni, A. Vouris, M. Yu
- LBNL: D. Cheng, P. Ferracin, E. Lee, M. Marchevsky, M. Naus, H. Pan, I. Pong, S. Prestemon, K. Ray, G. Sabbi, G. Vallone, X. Wang
- NHMFL: L. Cooley, J. Levitan, J. Lu, R. Walsh
- CERN
 - A. Ballarino, H. Bajas, M. Bajko, B. Bordini, N. Bourcey, J.C. Perez, S. Izquierdo Bermudez, S. Ferradas Troitino, L. Fiscarelli, J. Fleiter, M. Guinchard, O. Housiaux, F. Lackner, F. Mangiarotti, A. Milanese, P. Moyret, H. Prin, R. Principe, E. Ravaioli, T. Sahner, S. Sequeira Tavares, E. Takala, E. Todesco



Outline

- AUP Scope & MQXFA Magnets
- MQXFA Magnet Production status
- Lessons Learned
- Conclusions



3

US Contribution to HL-LHC



- HL-LHC: from 300 fb⁻¹ to 3000/4000 fb⁻¹
- LARP (DOE supported R&D Program) established the necessary technology for the HL-LHC Focusing Magnets and Crab Cavities
- DOE baselined HL-LHC AUP Project, coordinating efforts from US Labs (FNAL, BNL, LBNL with contributions from SLAC, JLAB, ODU & FSU)



Slide by G. Apollinari

MQXFA Magnets for HL-LHC Inner Triplets

10 Q1/Q3 Cryo-assemblies (including 2 spares)



MQXFA/B Design

PARAMETER	Unit	MQXFA/B		
Coil aperture	mm	150		
Magnetic length	m	4.2/7.15		
N. of layers		2		
N. of turns Inner-Outer layer		22-28		
Operation temperature	K	1.9		
Nominal gradient	T/m	132.2		
Nominal current	kA	16.23		
Peak field at nom. current	Т	11.3		
Stored energy at nom. curr.	MJ/m	1.15		
Diff. inductance	mH/m	8.26		
Strand diameter	mm	0.85		
Strand number		40		
Cable width	mm	18.15		
Cable mid thickness	mm	1.525		
Keystone angle		0.4		



Nb₃Sn Conductor B-OST RRP

P. Ferracin et al., "Development of MQXF, the Nb₃Sn Low- β Quadrupole for the HiLumi LHC " IEEE Trans App. Supercond. Vol. 26, no. 4, 4000207

G. Ambrosio et al., "First Test Results of the 150 mm Aperture IR Quadrupole Models for the High Luminosity LHC" NAPAC16, FERMILAB-CONF-16-440-TD

AU

2020 - Nov 3, 2020

Technical Progress: Nb₃Sn Superconductor, Coil Parts and Coils Assembly

- All Nb₃Sn Conductor is under procurement.
 - Delivered according to plans and meeting technical specs.
- Cable fabrication ~50% complete with 98% yield [1]
- Coil parts in stock at ~50+% level
- Coil fabrication is ~34% complete with yield *improving* to 78-80% levels (up from 75% in early stages of production).

Shipment A Shipment B Shipment A Shipment A	Jan-19 Jan-29 Jan-19 Feb-19 <u>B-OST dates</u> Sep-18 Sep-18 Sep-18 Jan-19 <u>B-OST dates</u> Feb-19 Mar-19 Jul-19 Jul-19 Jul-30	28 29-32 UL# 13-27 UL#	1 4
Shipment A Shipment B Shipment A Shipment A	jan-19 jan-19 Feb-19 B-OST dates Sep-18 Sep-18 Sep-18 Jan-19 Mar-19 Mar-19 Jul-19 Mar-19 Jul-19 Mar-19	28 29-32 UL# 13-27 UL#	1 4
Shipment A Shipment B Shipment A Shipment B	Jan-19 Feb-19 B-OST dates Sep-18 Jan-19 B-OST dates May-19 Mar-19 Jul-19 Mar-19 Jul-30	28 29-32 UL# 13-27 UL#	1 4 4
Shipment B Shipment A Shipment B	Feb-19 B-OST dates Sep-18 Sep-18 Jan-19 B-OST dates Feb-19 Mar-19 Jul-19 Jul-39 Mar-19	29-32 UL# 13-27 UL#	15
Shipment A Shipment B	<u>B-OST dates</u> Sep-18 Sep-18 Jan-19 <u>B-OST dates</u> Feb-19 May-19 Mar-19 Jul-19 Mar-19	UL# 13-27 UL#	15
Shipment A Shipment B Shipment C	Sep-18 Sep-18 Jan-19 B-OST dates Feb-19 May-19 Mar-19 Jul-19 Mar-19	13-27 UL#	15
Shipment A Shipment B Shipment C	Sep-18 Jan-19 B-OST dates Feb-19 May-19 Mar-19 Jul-19 Mar-19	13-27 ULU	15
Shipment A Shipment B Shipment C	Jan-19 B-OST dates Feb-19 May-19 Mar-19 Jul-19 Mar-19 Mar-19	13-27 UL#	15
Shipment A Shipment B	<u>B-OST dates</u> Feb-19 May-19 Mar-19 Jul-19 Mar-19	ULE	
Shipment A Shipment B	Feb-19 May-19 Mar-19 Jul-19 Mar-19		
Shipment A Shipment B Shipment C	May-19 Mar-19 Jul-19 Mar-19		
Shipment A Shipment B	Mar-19 Jul-19 Mar-19		
Shipment A Shipment B Shipment C	Jul-19 Mar-19		
Shipment A Shipment B	Mar-19		
Shipment B		33,34	2
Shinment C	Apr-19	35,36,37	3
and providents to	Jul-19	38,39,40,41	4
Shipment D	Oct-19	42-51	10
Shipment E	Nov-19	52-61	10
	B-OST dates	ULE	
	Jan-20		
	Apr-20		
	Feb-20		
	Jun-20		
Shipment A	Apr-20	62,63,64,65	4
Shipment B	Jun-20	66,67,68,69	4
Shipment C	Aug-20	70,71,72,73	4
Shipment D	Oct-20	74,75,76,77	4
Shipment E	Dec-20	78,79,80,81	4
	B-OST dates	UL#	
	Oct-20		
	Dec-20		
	Nov-20		
	Jan-21		
Shipment A	Feb-21	82,83,84,85,86a	4.5
Shipment B	Apr-21	86b,87,88,89,90	4.5
Shipment C	Jun-21	91,92,93,94,95a	4.5
Shipment D	Aug-21	95b,96,97,98,99	4.5
Shipment E	Oct-21	100,101,102,103,104a	4.5
Shipment F	Dec-21	104b,105,106,107,108	4.5
			96
	Shipment D Shipment C Shipment D Shipment A Shipment A Shipment B Shipment C Shipment C Shipment F TOTAL	Shipment C Aug-20 Shipment D C-20 Shipment D C-20 Shipment B Dec-20 Oct-20 Nov-20 Shipment A Feb-22 Shipment A Feb-22 Shipment C Jun-22 Shipment E Oct-22 Shipment E Oct-22 Shipment E Dec-22 TOTAL	Japanetic Description Shipment D Cd: 20 74,75,76,77 Shipment E Cd: 20 74,75,76,77 Shipment E Apr.21 866,87,88,89,50 Shipment A Feb-21 82,83,84,85,86a Shipment C Jun-21 91,92,93,94,45a Shipment E Oct-21 1060,105,106,107,106 York A Feb-21 82,23,94,45a Shipment E Oct-21 1060,105,106,107,106 TOTAL Example A



¹⁾ I. Pong et al., "Bare Cable Fabrication Statistics for the AUP MQXF Magnet Coils at 50% Milestone" this conference Wk2LPo3F-04

MQXFA Pre-Series Magnet Status

MQXFA03:

1st pre-series magnet

1st magnet completely fabricated by AUP

Status: cold test is complete, magnet is at FNAL

accepted for use in 1st Cold-Mass

MQXFA04:

Status: cold test at BNL is complete

MQXFA05:

Status: assembly is complete, magnet is at BNL

MQXFA06:

Status: assembly to be completed at LBNL in Dec 2020

MQXFA07 and Series Magnets:

Plans: a new magnet completed every other month



MQXFA03 & MQXFA04 Quench History [1]

Requirement MQXFA-R-T-03: The MQXFA magnet must be capable of operating at steady state providing an integrated gradient of 556.9 T in superfluid helium (HeII) bath at 1.3 bar and at a temperature of 1.9 K. \rightarrow 16230* A + 300 A (margin) = 16530 A for 300 minutes

Requirement MQXFA-R-T-17: After a thermal cycle to room temperature, MQXFA magnets shall attain the nominal operating current with **no more than 3 quenches**.



*Nominal and ultimate currents of WP3 magnets CERN-EDMS 2114564

1) J. Muratore et al., "Test Results of the First Pre-Series Quadrupole Magnets for the LHC Hi-Lumi Upgrade." this session

MQXFA03 & A04 Test Summary

Requirements & Test Goals:

- Hold current at nominal current + 300 A (T-3)
- Ramp to/from I_nom at ±30 A/s (T-11)
- 150 A/s ramp down w/o quench (T-18)
- Temperature margin
- Magnetic measurement (O-2)
- Splice resistance < 1 nΩ (T-29)</p>
- Training memory (T-17)
- All other requirements

MQXFA03 was accepted for use in 1st LMQXFA



A03

A04

10

Below the Surface...

- Before MQXFA Pre-Series Magnets:
 - Several Nb₃Sn quadrupoles magnets with bladder & Key structure by the LHC Accelerator Research Program (LARP)



- One MQXF short coil and one long coil tested in "mirror magnet" by LARP
- Five MQXFS short models, many re-assemblies and many tests by LARP/CERN/AUP (S1a/b/c/d/e) and CERN (S3a/b/c, S4a/b/c, S5, S6a/b/c)
- <u>Two MQXFA prototypes by LARP</u> and one re-assembly by AUP
- One MQXFB prototype by CERN



Lesson Learned #1 – The Issues

Issue #1: In 1st prototype Coil-Ground short

- Causes: a dry spot after impregnation (experimental insulation) plus a high-voltage test (Hipot) at 300 K after He exposure performed at pre-cooldown value → caused a double Heater-Coil short [1], that caused Coil-Ground short
- Solution: Electrical Design Criteria has lower Hipot values after He exposure, and additional Hipot at 100 K in He gas after training and thermal cycle [2,3].
- Now: all quench heaters meet requirements
- Issue #2: Some early coils had coil-pole or coil-saddle electrical weakness
 - Causes: excessive binder at coil-pole interface; saddle exchange after winding
 - Solution: reduced binder amount close to pole; no more saddle exchange after winding

1) J. Muratore et al., "Test Results of the First Two Full-Length Prototype Quadrupole Magnets for the LHC Hi-Lumi Upgrade" IEEE Trans App. Supercond. Vol. 30, no. 4, 4004205

2) M. Baldini et al., "Assessment of MQXF Quench Heater Insulation Strength and test of Alternative Design" this conference Wk2LOr1B-06

3) V. Marinozzi et al., "Study of the heater-coil electrical insulation for the HL-LHC low beta quadrupoles" this conference Wk2LPo2I-08

Lesson Learned #1 – The Lesson

- Background info: Fabrication technology in use for MQXF coils was developed by LARP (LHC Accelerator Research Program). LARP performed Hipot test at 1 kV, which was the max at vertical test facilities used at that time
- Lesson Learned: During R&D make estimate of peak voltages <u>plus margin</u> for all high-voltage tests (Hipot, Impulse test, ...); and <u>perform tests</u> <u>at these levels as early as possible</u>.



13

Lesson Learned #2 – The Issue

Issue: In 2nd prototype bottom AI shell fractured during/after cooldown [1]

- Causes: shell manufactured incorrectly (sharp corners) and non-conformity was accepted based on past experience
- Solution: AUP Structural Design Criteria require large fillet radii (min 10 mm), ultrasound tests, die penetrant tests, cold property tests



1) D. Cheng et al., "Mechanical Performance of the First Two Prototype 4.5 m Long Nb3Sn Low- β Quadrupole Magnets for the Hi-Lumi LHC Upgrade " IEEE Trans App. Supercond. Vol. 30, no. 4, 4000906





Lesson Learned #2 – The Lesson

- Background info: Successful use of AI shells in many LARP short and long models generated confidence, but the addition of acceleratorquality features (cutouts) and the acceptance of a non-conformity generated this issue.
- Lesson Learned: <u>Develop Design Criteria</u> (Structural/Electrical/...) in the early phase of the R&D
- Al-shell-based structures can be used for accelerator magnets



Lesson Learned #3 – The Issues

- Issue: Actual coil yield (80%) is lower than in project baseline (87%)
 - Causes: Several different causes; only one station (winding at FNAL) had more than one issue per station
 - Solution: Winding equipment at FNAL was replaced; Corrective Action & Preventive Action implemented after every issue; Lessons Learned are shared in AUP and with CERN; increased QA resources; performed Electrical QA assessment; ...
 - Now: Coil yield is getting better



16

Lesson Learned #3 – The first Lesson

- Original assumption: after fabrication of coils for short models and prototypes, production coil yield is expected to be higher than in the R&D (LARP) phase. I.e. "we will be out of the learning curve after prototype phase"
- First Lesson Learned: equipment changes from short to long coils, and need to increase technician number may negatively affect coil yield in the early phase



Lesson Learned #3 – The second Lesson

- Second Lesson Learned: present coil fabrication technology for Nb₃Sn accelerator magnets is very labor intense
 - It is fine for a small series production (HL-LHC)
- A large-scale production of Nb₃Sn accelerator magnets must be preceded by the development of 2nd generation Nb₃Sn coil fabrication technology that should be <u>much less labor intense</u>
 - Automation may be part of the solution, nonetheless it will require significant effort to prepare the coil fabrication technology for this step



Conclusions

- Successful test of the first two MQXFA Pre-Series magnets for HL-LHC has demonstrated AUP readiness for Series production
- Some Lessons Learned have been instrumental to this progress
- ... and may be useful for future projects

Thank you!



Back up Slides



MQXFAP1 Short to Ground: Causes & Prevention

- Short was caused by a series of (now) well-understood events:
- Coil 5 impregnation was poor in the short area:
 - Increased possibility of helium trapped after cold test
 - Insulation brand/vendor no more used after this coil
- Between quench 1 and quench 2, magnet was hipotted with high voltage (2.5 kV) at room temperature, after helium exposure
 - Coil 5 failed during this hi-pot test
 - Helium at warm is a poor insulator
 - This procedure will not be repeated, according to AUP Electrical Design Criteria



- Hi-pot during training was performed because of rupture of the burst disk and subsequent warm-up
 - Helium relief system was upgraded and demonstrated

➔ The issue was caused by a combination of well-understood events, and each one will be prevented in future tests

Design weakness is excluded



Analysis on MQXFAP1 Short-to-Ground: US-HiLumi-doc-897 Failure Analysis of MQXF Heater-Coil Insulation: US-HiLumi-doc-921

MQXFAP2 Broken Shell

<u>Root cause:</u>

- LARP structure with bottom shell manufactured incorrectly and inspected before Final Design Report was completed
- Non-conformity (sharp corners) accepted (June 2017)
- Material temper different from other shells (under investigation)

Issue addressed in FDR (May 2018)

- 10 mm min fillet radius at critical corners
- Lesson learned: non-conforming parts will be rejected

Picture from MQXFA FDR, showing <u>10 mm fillet radius</u>



Longitudinal fracture in return-end shell with crack start at <u>sharp corner</u>





Low-β quadrupole magnets from LHC to HL-LHC

- Cold mass OD from 490/420 to 630 mm
- More than double the aperture: from 70 to 150 mm
- ~4 times the e.m. forces in straight section
- ~6 times the e.m. forces in the ends

State of the art quadrupoles at the time of LHC construction

MQXA



MQXB



Same scale for all 3 plots





MQXF

8-0-8