

Status of LBNF Beam

Keith Gollwitzer

Fermi National Accelerator Laboratory

NuFact 2021: The 22nd International Workshop on Neutrinos from Accelerators

10 September 2021

This manuscript has been authored by Fermi Research Alliance, LLC under Contract No. DE-AC02-07CH11359 with the U.S. Department of Energy, Office of Science, Office of High Energy Physics.



U.S. DEPARTMENT OF
ENERGY

Office of
Science



Outline

- Requirements
- Primary Beam
- Target Complex
- Decay Volume Structure
- Absorber Complex
- Instrumentation & Monitoring
- Civil Facilities

LBNF Beamline Requirements & Optimization of Parameters


- Design for initial delivery of 1.2 MW beam power; upgradeable to 2.4 MW.
- Proton beam energy between 60 GeV and 120 GeV
- Pulse length of ~ 10 μsec
- Proton beam size on target tunable 1.0 – 4.0 mm rms
- Beam Optimization was performed to maximize DUNE physics (with some engineering constraints)
 - Three focusing horn system (geometry and spacing part of optimization)
 - Target inserted in first horn
 - Magnetic field generated by a 300,000 A pulse (half-sine wave of 800 μsec ; beam at flat-top)
 - Target to be cylindrically symmetric
 - Graphite material
 - Length of target desired to be four interaction lengths

LBNF Beamline



LBNF Near Site


Primary Beam



Apex of Proton Beamline is 17.5 m above Main Injector


From Apex to target, beam drops 6 m & is at correct downward angle (101 milliradian) directed at DUNE detectors

Primary Beam




International Partners for Magnets


- Dipoles and Quads
 - BARC of India
 - Based upon previous Fermilab designs
 - Prototype fabrication about to begin
- Correctors
 - IHEP of China
 - Developed, produced, & delivered



Target Complex: Target Hall and Chase




Scope in Target Complex – Support Rooms



Target

- UKRI is providing the Target (prototype and production)
- Settled upon using a cantilevered target based upon previous work (T2K)
 - Any downstream support absorbs too much
 - Will build prototype of 1.5 m length (50% longer than T2K)
 - After prototype build and testing, will decided production target length
 - Desired to be 1.8 m to achieve four interaction lengths



'Baffle':

- Protects downstream elements
- enables 'beam based alignment'

Container:


- Titanium alloy including beam windows

Target:

- Segmented graphite rod

Prototyping Helium Cooling Gas Manifold – Manufacturability

cold helium in




UKRI is moving forward with other prototyping before building a 1.5 m prototype T= target




Focusing Horns

Have started building a Horn A Prototype




Horn A





Horn B

Integration of Target into Horn A

Green target module flange mates directly to **red** pre-aligned mounting plate on the horn.




Specialized Equipment to remove and install target assembly remotely




Need to remove/insert target without touching inner conductor, attach to flanges, connection of gas cooling line, & connection of instrumentation lines

Support Structure

- Securely holds component
- Allows positioning component precisely
- Provide pathway for utilities
 - Stripline bus (300,000 A)
 - Cooling
 - Water cooling for horn
 - Helium cooling for target
 - Thermocouple instrumentation
- Wall are part of radiation shielding
 - Other shielding fill in
- Connections are all done via Remote Handling




Remote Handling in Work Cell



Other Recent Prototyping work


Electrical Bus & Ceramic Isolator Testing





Remote Clamp Joint



Ejection lines draw water ~8.2 meters




Water Tank



Decay Volume

Decay Volume is 194 meters in length

Filled with Helium




Two concentric steel tubes
separate the helium volume from
the shielding.

Surrounded by > 5.6 meters of concrete shielding.

Cooling of the steel tubes is by nitrogen gas

Absorber Complex


Old plan; service building has changed



Absorber Hall Floor is 25 meters below ground


Hadron Detector in front of absorber

- Used for Beam Based Alignment
- Able to lower into position when needed
- Replaceable



Absorber is a series of Aluminum and Steel Panels

- Water cooled
 - Drilling pattern shown
 - Plug/weld 16 holes
- Replaceable panels
- Designed for 2.4 MW



Facility Instrumentation and Monitoring

- Three muon stations behind absorber
 - Samples high energy muons that are produced
 - Look for changes in muon distributions
 - Determine muons produced per proton on target
- Thermocouple array distributed through absorber
 - Able to monitor protons not interacting with the target
- Hydrostatic Level System
 - Monitor movement of Target Station components with respect to final focusing elements of proton beamline
 - Vertical movements of components due to motors and thermal expansion
- Beam Based Alignment System
 - Includes features on Horns, Target, & baffle to scan beam across
 - Includes retractable beam loss monitors in target chase area

Civil facilities

- Intense design work over the last year
- Concentration on radiological issues
 - Building has permanent shielding
 - Control of radioactive gases
 - Defining air flow path to allow isotopes to decay before release to atmosphere
 - Provide a buffer volume between the radioactive air path and the atmosphere
 - Control of water and ability to test water before directing to outside or to be captured
 - Water seepage into facilities
 - Condensate from air handling units

What is for 1.2 MW and 2.4 MW

- What is design for 1.2 MW and could be replaced with a future upgrade
 - Baffle
 - Target
 - Horns
 - Beam windows of Target chase
 - Instrumentation/Detectors
 - Some cooling Systems
- What is designed for 2.4 MW and should not have to be replaced
 - Proton beamline components
 - All shielding
 - Piping for cooling systems between support rooms and components
 - Decay Volume
 - Absorber
 - Power Supply

Final Remarks

- LBNF Beamline is part of the LBNF/DUNE-US Project
- The LBNF Beamline is based upon the experiences of other neutrino beamlines
- Prototyping is in progress
- Facility will support initial beam power of 1.2 MW and is upgradeable to 2.4 MW