

# **Borexino at Gran Sasso**

## **A real time detector for low energy solar neutrinos**

**Gioacchino Ranucci**

**Neutrino 2000**

**Sudbury 6 - 16 - 2000**

### **Summary**

- **Description of the detector**
- **Physics program**
- **Radiopurity issues**
- **Status of the installation**
- **Conclusions**

# Borexino Collaboration

✓ Belgium

I.R.M.M. European Joint Research Centre - Geel

✓ France

College de France

✓ Germany

Max-Planck-Institut Für Kernphysics Heidelberg  
Technische Universität München

✓ Hungary

KFKI-RMKI Budapest

✓ Italy

Dipartimento di Fisica e INFN Genova

Lab. Naz. INFN del Gran Sasso

Dipartimento di Fisica e INFN Milano

Dipartimento di Fisica e INFN Pavia

Dipartimento di Fisica e INFN Perugia

✓ Poland:

Jagellonian University Krakow

✓ Russia

JINR Dubna

Kurchatov Intitue - Moscow

✓ United States

Bell Laboratories, Lucent Technologies

Massachusetts Institute of Technology


Princeton University

Virginia Polytechnic Institute

# Borexino

**A real time, calorimetric, scintillation detector, for low energy solar neutrinos, under installation at the Gran Sasso underground Laboratory, aimed at the detection of the monoenergetic  ${}^7\text{Be}$  neutrinos, through scattering off the electrons of the scintillator**

# Expérience Borexino



# **Main Components: Detector**

**Scintillator**

**Nylon (Inner and Outer) Vessels**

**Buffer Liquid**

**Stainless Steel Sphere**

**support of PMT's**

**containment of the buffer (zero**

**buoyancy for the nylon vessels)**

**PMT's**

**Concentrators**

**Muon veto**

**Calibration equipments**

**Water Tank**

**Electronics and DAQ**

# **Main components: Plants**

**Storage Vessels**

**Scintillator Purification systems**

**Water extraction**

**Distillation**

**Column purification**


**Nitrogen sparging**

*N<sub>2</sub> PLANT*

**Fluid Handling System**

**Water Purification System**

**Clean room**



- BX > Tank for BOREXINO
- BB > Building for electronics equipments
- CTF > Counter Test Facility
- CR > Clean-Room for CTF
- S > Storage Area for Pseudocumene Scintillator
- H > Tunnel Section (Hall-C)
- W > Crane

# Scintillator

**Solvent : Pseudocumene**

**Solute: PPO (1.5 g/l)**

**Light yield: 11000 ph/MeV**

**Att. Length (@420): 30 m**

**Scatt. length (@420 nm): 7 m**

**Decay Time (fast component) : 3.5 ns**

**Good  $\alpha$   $\beta$  properties**



## Photomultipliers

8" Electron Tubes Limited 9351 type

P/V : 2.5

Transit Time Spread: 1 ns

Dark Count rate: 1kHz

Afterpulsing < 3%

Low radioactive glass and internal parts

## Light Concentrators

Truncated string cone design

Optimized to collect the light from the inner vessel and 20 cm beyond it

Material: anodized aluminum

## Mesured quantities

The electronics measures and provides for each triggered event :

- the photomultipliers pulse height  
⇒ energy measurement
- the photoelectrons arrival time  
(0.3 ns resolution)  
⇒ location identification
- the absolute time of the event

## Expected detector performances

Effective Coverage: 30%

Photoelectron yield: 400 pe/MeV

Energy resolution (@ 1MeV): 5 %

Position resolution (@ 1 MeV): 10 cm

# Calibrations

A variety of calibration and monitoring systems are planned:

✓ Laser pulses distributed to all PMT's with a fiber optics splitting system

- timing calibration
- gain adjustment via detection of the single photoelectron peak

✓ External sources (Th) located in the S.S.S close to the light cones

- check of the stability in time of the overall detector response

✓ Internal sources inside the scintillator

- position calibration
- energy calibration
- $\alpha/\beta$  PSD determination

## Calibrations

✓ Laser beams with different wavelengths through the buffer and laser excitation of the scintillator

- stability monitoring of optical properties

✓ Blue LEDs on the external tank for the outer muon veto detector


✓ Active tags of trace impurities in the scintillator

- cross check of the absolute energy scale determination
- additional stability monitor

✓ Calibration of the overall detector response via a sub-MeV  $\nu$ -source ( $^{51}\text{Cr}$ )

## Neutrino Detection in Borexino

Detection through the scattering reaction



off the electrons of the scintillator

The **high luminosity** and **high radiopurity**

of the scintillator lead to a low detection threshold: **250 keV**.

It is possible to detect the recoil electrons produced by the monoenergetic (**0.861 MeV**)  ${}^7\text{Be}$   $\nu$ .

Maximum recoil energy: **0.66 MeV**

SSM prediction: **55 ev/d** for 100 T F. V


# The Borexino program

- First direct measurement of  ${}^7\text{Be}$  flux

Expected rates (ev/d) in a F.V. of 100 T

Recoil Energy window MeV	SSM	LMA	SMA	LOW	VO
		$\Delta m^2 = 1.8 \times 10^{-5}$ eV <sup>2</sup> $\sin 2\theta = 0.76$	$\Delta m^2 = 5.4 \times 10^{-6}$ eV <sup>2</sup> $\sin^2 \theta = 5.5 \times 10^{-3}$	$\Delta m^2 = 7.9 \times 10^{-8}$ eV <sup>2</sup> $\sin^2 \theta = 0.96$	
0.25 - 0.8	55.2	30.7	11.7	29.0	
				day/night effect	seasonal variation



- Probing vacuum oscillations via seasonal variation of the flux
- In absence of other time variations, demonstration of the solar origin of the signal through the 7% variation due to the Earth-Sun distance variation during the year
- Background  $\sim 15$  ev/d



## Other capabilities

⇒  ${}^8\text{B}$  spectrum in the unique energy window 1.5-5 MeV

⇒ Antineutrino Science



Search for solar  $\bar{\nu}_e$

Geophysical  $\bar{\nu}_e$  from the Earth

$\bar{\nu}_e$  from Type II Supernovae

Long-baseline  $\bar{\nu}_e$  from European reactors



## Radiopurity of the scintillator

Main issue for the feasibility of the experiment

Purity requirements for  $^{238}\text{U}$  and  $^{232}\text{Th}$  in the range of  $10^{-16}$  g/g

Laboratory measurements on small samples:  $2-3 \times 10^{-15}$  g/g  
mainly limited by impurities leached from the wall of the vessels

Needed a direct measurement on some tons of scintillator with a sensitivity level at least  $5 \times 10^{-16}$  g/g  $\rightarrow$  CTF

Further high sensitivity measurements performed with **Neutron Activation Analysis**

## Achievements of CTF

### 1 - Demonstration of unprecedented purity levels

$$^{14}\text{C}/^{12}\text{C} = (1.94 \pm 0.09) \times 10^{-18}$$

$$^{232}\text{Th} < (4.4 \pm 1.5) \times 10^{-16}$$

$$^{238}\text{U} < (3.5 \pm 1.3) \times 10^{-16}$$

### 2 - Demonstration of the effectiveness of the planned purification methods for Borexino

#### Purity levels confirmed with Neutron Activation Analysis

$$^{238}\text{U} < 2 \times 10^{-16}$$

CTF has been recently reinstalled for quality control of the scintillator prior to detector filling

# Status of the experiment preparation

**Scintillator components (PC and PPO): manufacturers identified, contracts under finalization**


**Nylon (Inner and Outer) Vessels: test prototypes already produced, material selection almost completed**

**Stainless Steel Sphere: construction completed, final surface treatments in progress**

**PMT's:**

**bare devices: 90% ready**


**PC/water proof encapsulation: designed, tested for 6 months in the "two liquid test tank"**



**Prototype of the Inner Nylon Vessel**




**Stainless Steel Sphere inside the Water Tank**





# Installation of the Two-Liquid Test Tank



**PMTs & optical fibers mounted in the TLTT**

# Status of the experiment preparation

**Water tank: completed**


**Electronics and DAQ: hardware and software ready, final integration in progress**

**Muon veto: dedicated PMT's and electronics in preparation**

**Concentrators: under production**

**Calibration equipments: in preparation; optical fiber system tested in the "two liquid test tank"**







# **Status of the experiment construction**


**Storage Vessels: completed**

**Scintillator Purification Systems: in advanced phase of installation, test foreseen in the next fall with CTF, for column purification test already started**

**Fluid Handling System: ready by the Fall**

**Clean room: under construction, to be completed by end of August.**





## Conclusions

- ✓ The design of all the experiment subsystems has been finalized
- ✓ Major installations have been already completed in Hall C
- ✓ All the other equipments to be installed are in preparation/installation phase
- ✓ Borexino ready for filling by middle of next year
- ✓ CTF rebuilt, ready for qualification of the scintillator and for test of the purification system