


Figure 1. Schematic view of BOREXINO. The ultrapure scintillator (300t) inside a nylon vessel is shielded differentially by means of a liquid buffer (1040t), a steel sphere on which the tubes are mounted, and the outer water buffer which is contained in an external steel tank with dimensions of about 18m. A transparent nylon shroud hinders radon convection in the liquid buffer region. Additional tubes mounted on the outer surface of the steel sphere allow detection of penetrating muons via the Cherenkov effect.



Radiopurity

Scintillator:


- ¹⁴C in the range: 10⁻¹⁸
- U, Th at $\sim 10^{-16}$ g/g
- K at $\sim 10^{-12}$ g/g
- Rn μBq range

Buffer liquid:

- U, Th ~ $10^{-15} 10^{-14}$ g/g
- electropolished, roughness $\rightarrow r_a \sim 0.4 \mu m$
- tightness single component ~ 10⁻⁸ st cm³/s
 (underground Rn: 40-80 mBq in air)
- cleanliness
 class 10-50 Mil. St. for the surfaces
- 4Cr class 10-1000
 - SSS class 5000









PMT's and electronics

- The 2414 PMT's almost installed (160 left in the inner detector and 140 left in the outern muon veto: waiting for the I.V. installation) – infant mortality < 1%
- Leak checks of all flanges successfull
- Arrival time and collected charge from PMT

 First and alected charge from PMT

 Arrival time and collected charge from PMT


 Arrival time and collected charge from PMT


Front-end electronics, 8 bit ADC (range → 3 MeV)
Trigger → coincidence in a time< 50 ns


tested and tuned during 2 "air runs" (one week each) successful DAQ tested successfully


- Analog sum of 50 PMT's: FADC (range → 20 MeV)
 - · FADC will be installed in June
- Outer muon electronics: ready in July











Calibration

1. timing calibration

394 nm laser 35 fibers (6 spares) → 90 fibers each

test: > 99% of the fibers run properly

- 2. transparency monitor system (TMS)
 - 2 lasers (394 and 355 nm) via 31 optical fibers convey the light on 31 SSS points crossing the scintillator and the buffer liquid.

installed and tested

Monitor of the scintillator response
 laser (266 nm) via 1 optical fiber within the Inner Vessel

(installed), tested

4. Positioning System (6 CCD cameras)

installed

Internal Source Insertion System (SIS)
 Installation during the water filling

in construction phase





Scintillator properties

Pseudocumene + PPO (1.5 g/l)

Light yields: 380 photoelectrons/MeV

¹⁴ C	1.8 ± 0.09	x 10 ⁻¹⁸	¹⁴ C/ ¹² C	
	1.34 ± 0.01	**	44	
	2.6 ± 0.2	44	66	
	4.7 ± 0.2	44	**	

Absorption length > 8 m

Brom index < 5

 O_2 content $< 10^{-5}$ g/g




PC

- 300 mc (for the scintillator) procured within end of June;
- stored in 3 of the 4 silos of the storage area (100 mc each)
- 4th silo used for the PC (or scintillator) movements during the purification (s)

PPO

- procured (1.5 g/l)
- master solution prepared and prepurified in the PPO plant (water extraction + stripping)
- master solution purified through a water extraction + stripping system
- also sigel column can be used for the purification
- added to PC either in the storage area or during the Borexino filling





Purification systems

Water

tested in CTF

Rn: 25 mBq/mc

Ra: < 2 mBq/mc

Within the shroud:

 $2. \pm 0.5 \text{ mBq/mc}$

- Scintillator
- water extraction
 in testing phase
- silicagel column
 tested in continuous mode
 next test in batch
- PC
- distillation

to be tested

N₂

regular R_μ: 80-100 μBq/mc

• ultrapure R_m : $0.3 \pm 0.1 \,\mu\text{Bq/mc}$







Nylon Vessels

Inner vessel: nylon 6 co-polymer (Sniamid)

diam. 8.5 m

thickness 125 µm U,Th: ~ 1 ppt

Shroud: nylon 6 (Capron)

diam. 11 m

thickness 125 µm w, Th: ~ 15 ppt

Light trasmittance: > 90%

Haze <2%

Nylon becomes brittle if dry:

humidity: 50% during the construction

> 60% during the installation

20-30% in operation

Rn diffusion: diff. length: 10 µm at 20-30% of humidity

100 µm at 90% of

Buoyancy: 0.4% of density difference

5 °C of difference in temperature







Filling

- Purify the scintillator before the filling and test it with CTF
- Two possibilities: → PPO added to PC during the filling
 - → PPO added in the storage area
- Possible final purification during the filling (emanation of the vessels and pipes)
- First filling with water (easiest recovery in case of problems maximum stress of the I.V. during the first filling)
- Replace water with PC: → PC from the top
 - → water from the bottom
- Contemporary filling of the buffer PC after a stripping (~ 1000 mc)
- Mixing with DMP during the buffer filling (~5 g/l).



Safety


- · Strong effort on the safety systems and on the procedures
- 5 fire systems, each of them redondant
- Double containing for all systems handling PC also temporarily
 → <10⁻⁶ probability of leakage everywhere.
- All vapors purified through charcoal with final check via analyzer
- · Bleeding and waste systems
- Possible heavy earthquake (0.3 g) taken into account in the design



Operation sequence

- Nylon vessels installation: July and August (first half)
- Filling with water: August, September
- Scintillator preparation and purification: since October
- PC filling: start November 2002 and April-May 2003
- Study of the background during the filling





The "Borexino" program

Main interaction:

$$v_x + e \rightarrow v_x + e$$

Measurement of the v from ⁷Be

250-800 KeV

• Rates expected (ev/day):

927	S.S.M. (B.P.)	MSW-SMA	MSW-LMA ±3 σ	MSW-LOW ±3 σ	VO ±3 σ
With SK total rates	55	12 ⁺¹⁶ _{-0.5}	32+7	26	38 ⁺¹⁵ ₋₁₀
Before SNO			36+5	32 ⁺⁷ ₋₃	32 ⁺⁹ ₋₄
After SNO			35+5	32±3	32 ⁺⁵ ₋₄

Expected background: ~15 ev/day

• Day/night (%)

	LMA	LOW	
Before SNO	0.0+0.1	15+17	
After SNO	0.0+0.1	23+10	

Seasonal variation (VO)

Measurement of the v from ⁸B:threshold at 3.5 MeV – expected rate: ~60-125 ev/year.



