# GALLIUM-EXPERIMENTS GALLEX / GNO

$$v_e + {^{71}Ga} \rightarrow {^{71}Ge} + e^{-}$$

i = 39.6 %;  $T_{1/2} = 11.43 days$  threshold energy: 233 keV

**SSM-Expectation:** 

 $130 \pm {}^{9}_{7} \text{ SNU } (1\sigma)$  [B.G.P.01]new <sup>8</sup>B

[1 SNU = solar neutrino unit = 10<sup>-36</sup> captures per target nucleus per second]

55.8 % from pp - V (incl.pep) (72.5 SNU)

26.3 % from <sup>7</sup>Be (34.2 SNU)

7% from CNO - v (9 SNU); 11 % from <sup>8</sup>B (14 SNU)

100 tons of aqueous Gallium chloride solution (= 30.3 t Gallium);

correspond to a SSM-production rate of 1.18 atoms of <sup>71</sup>Ge per day or

≈14 atoms at the end of a 3-week exposure

Extraction every 3 - 4 weeks ,  $\epsilon \cong 99 \%$ 

CNO

**B8** 


Be7

pp

# Why sub-MeV - Neutrinos ?

- $\star$  98 % of all solar neutrinos are sub-MeV ( $\Phi_7 \sim 7$  %,  $\Phi_{pp} \sim 91$  %)
- → The flux is constraint by the solar luminosity. There is no need to chose a specifically constrained solar model.
- → To the contrary, the measured fluxes can lead to more stringent limitations of departures from the standard solar model, especially if the flux of converted neutrinos could be deduced with Borexino precision measurements (combination of Bx + Ga +Cl experiments).

- → The sub-MeV range is particularly discriminating among the various neutrino oscillation parameters that are still allowed by the presently available experimental data. So far this dominant part of the solar neutrino spectrum is explored only with Gallium, soon to be followed by Borexino for the <sup>7</sup>Be part
- → There is a high exploratory potential for time variations (day/night: espec. Borexino, seasonal: GNO).
- → All this will take time, but no practical competition to explore the sub-MeV region is seen in the next 5 years, with the possible exception of "High purity-Kamland", which would not differ in the principal approach.



# Determination of the pp- neutrino flux from GNO and Borexino


Experi- ment	Threshold [keV]	<b>pp-</b> ν (0-420 keV)	<sup>7</sup> <b>Be-ν</b> (862 keV, 90%)	
GNO	233	ν <sub>e</sub> <b>c.c.</b> ν <sub>μ, τ</sub> -	ν <sub>e</sub> <b>c.c.</b> ν <sub>μ,τ</sub> -	
Borexino	500 (E <sub>v</sub> )	ν <sub>e</sub> -	$v_e$ c.c.,n.c.* $v_{\mu,\tau}$ n.c.*	

<sup>\*</sup> n.c.- sensitivity  $\approx 1/6$ .

#### radiochemical

## **GNO**


#### inverse β- decay CC



#### real time


### **BOREXINO**

#### v - e scatt. CC




$$\sigma \approx 5.3 \cdot 10^{-45} \text{cm}^2$$

#### v - e scatt. NC



$$\sigma \approx 1.10^{-45} \text{cm}^2$$



i. $\beta$  = inverse  $\beta$ -decay; e.s.= electron-scattering; g+e = ground st.+ exc. st.

#### **GALLEX - RESULT**

# 78 ± 8 SNU (1σ)

= (59 ± 6) % of the SSM-EXPECTATION; = 105 % of pp - EXPECTATION

#### SIGNAL

HYDROGEN - FUSION IN THE SOLAR INTERIOR OBSERVED

#### **DEFICIT**

DEFINITE DEFICIT OF <sup>7</sup>Be- (or pp-) NEUTRINOS OBSERVED: Not explainable by Solar Physics

# Data status and recent progress in GNO

GNO is the modernized and improved continuation of the GALLEX experiment at Gran Sasso

- → newly structured collaboration
- → new analog electronics
- new digital electronics; one Transient Digitizer for each line; led to much improved pulse shape recording
- → In-shield counter calibration with X-ray tube
- → Improved internal radon correction
- → Internal calibration of individual counter efficiencies\*
- → Neural network pulse shape analysis\*

\* in progress

# Principal goals

- 1. separation of pp and <sup>7</sup>Be fluxes
- 2. significant exploration of presence or absence of time variations (D/N; seasonal; solar parameters,..)
- 3. CC/NC ratio for bulk solar flux

#### What must be done?

- 1. Error reduction statistical
- 2. Error reduction systematic
- 3. Error reduction cross section

#### **GNO**

## (a) Statistical errors:

Continue measurements for full solar cycle [ongoing] increase target mass (\$€ or joining existing Ga experiments) [pursued]


## (b) Systematical errors:


Reduce counter efficiency errors by new ('more daring') procedures [ongoing] and/or by new counting concepts [R&D ongoing].

note: little gain is expected from further counter background improvement because the latter can not get negative


(c) Production cross section errors:

Advanced MCi neutrino source exposure for more precise determination of excited state contributions [ongoing]





# 43 GNO Runs $^{71}\tau = 16.7 \pm 3 \text{ d}$ $^{71}\tau_{\text{true}} = 16.49 \text{ d})$





# **GNO**

fast events occuring at t < 50 days

fast events occurring at t > 50 days

 $(50 d \approx 3 \tau)$ 





 $L_{only}:69.6\pm10.3~SNU$ 

 $K_{only}: 62.2 \pm 8.2 \text{ SNU}$ 

L+K:  $65.2 \pm 7.1$  SNU (N.N.)

L+K:  $69.4 \pm 7.1$  SNU (R.T.)

#### **GNO II** Blank Runs

Why Blank Runs?

To check each 3 month the proper functionality of the whole setup (no tailig effect, background from isotopes other than <sup>71</sup>Ge, ecc)

Run	Start exp. End exp.	Exp Time [d]	Chem Yield [%]	Counting [d]	Excs Cnts	Bckg Cnts 160 d
A023	12-01/13-01-00	27	91.2	165	1.4	8.6
A027	5-04 / 6-04-00	28	94.8	166	0.0	15.0
A031	28-06 / 29-06-00	28	97.7	164	0.0	11.0
A035	20-09 / 21-09-00	27	94.7	166	1.7	5.3
A039	12-12/13-12-00	28	93.0	165	1.3	8.7
A043	7-03/8-03-01	28	98.1	166	0.7	9.3
					3.7	59.3
				Average per run	0.85 ± 0.73	9.65 ± 3.2

NN pulse shape

# Summary of systematic errors in GNO (SR1 – SR43)

Neutrino 2002

ITEM	GNO	GLX	GNO+ GLX	
Target size	0.8 %	0.8 %		
Chemical yield	2.0 %	2.0 %		
Energy cuts	2.9 %	4.0 %		
Pulse shape cuts ev. sel. (others)	1.3 %(NN) 0.6 %	2.0 % 0.3 %		
Subtotal	4.0 %	5.0 %	4.6 %	
Side react. Rn cut ineff. 68Ge	1.2 snu 0.8 snu –	1.2 snu 1.2 snu +0.7 snu +2.0 snu		
Subtotal	1.4 snu	+1.8 snu -2.6 snu	1.9 snu	
Rate (SNU) stat. err. (SNU) sys err. (SNU)	65.2 6.4 3.0	77.5 6.2 4.5	70.8 4.5 3.8	
Tot err. (SNU) Tot err. (%)	7.1 10.9	7.6 9.8	5.9 8.2	
# of solar runs	43	65	108	

#### GNO main results

- → High performance duty cycle now for 3.7 years
- → Substantial reduction of systematic error to 4.6%
- → 14 GNO Blank runs, zero-compatible
- $\rightarrow$  Result from 43 runs (from 5/98 through 1/02) is


 $65.4 \pm 6.5_{st} \pm 3.0_{syst}$  or  $65 \pm 7$  SNU

## GALLEX + GNO combined (108 runs)

 $70.8 \pm 4.5_{st} \pm 3.8_{syst}$  or  $71 \pm 6 SNU$ 

→ No seasonal variation:

Winter - Summer =  $-11 \pm 9$  SNU



depression factor = .57

#### Future Plans in GNO

- → Further reduction of systematic error to 3% within 2 years (completion of internal counter calibrations and implementation of neural network analysis). Later: new cryogenic <sup>71</sup>Ge detection (efficiency gain up to 35%).
- ightarrow continued exploration of joining Gallium from Sage and GNO in one experiment: potential for 100 t Ga experiment, for a statistical error of  $\pm$  4 SNU
- New 3 MCi  $^{51}$ Cr source experiment for cross section determination to  $\pm$  5% rem: Gallex result: (89  $\pm$  7)%. (this is a true cross section due to the results from the Gallex  $^{71}$ As experiment (chemical recovery 100  $\pm$  1%)

Allows also a model independent proof of non-standard neutrinos from Gallium alone (exclusion of 'minimal' model,  $\approx$  90 SNU [2 $\sigma$ ] )

# New GNO Calibration 2002/2003


<sup>51</sup>Cr Source Production at RIAR, 2.5 – 3 MCi from 11 kg Cr (38% <sup>50</sup>Cr)

Determination of absolute cross section with error  $\leq 5\%$ Important for splitting of GNO signal in pp – and <sup>7</sup>Be - contributions


- → A 'real' calibration
- → a stepping stone for a full LNGS neutrino source program
- → also a check of 'ageing' of the target after 7 years of operation

# Cryogenic detectors for GNO

2 Ir/Au transition edge sensors



- $4\pi$ -efficient setup with 2 absorbers
- counting efficiency 98%
- deposition by CVD:  $GeH_4 \rightarrow Ge + 2H_2$
- deposition efficiency ~ 95% in 3h



# Status of cryo-GNO

- detector geometry for 4π absorption
- Ge deposition (compatibility with the existing chemistry)
- determination of the deposition efficiency on a 1% level
- detailed understanding of spectra
- decoupling of fabrication and Ge deposition
- · long-term stability of cryostat
- background investigations, detector shielding, material selection
- long-term operation of detector system













ongoing activity