

# The MINOS Experiment

- The NuMI beamline
- The MINOS Detectors
- Some first data!
- Physics Measurements
- Atmospheric  $\nu$  vs  $\bar{\nu}$ .
- Summary


Douglas Michael  
California Institute of Technology  
Neutrino 2002  
Munich  
May 27, 2002

# The MINOS Experiment

- Precision measurements of:
  - Energy distribution of oscillations
  - Measurement of oscillation parameters
  - Participation of neutrino flavors
- Direct measurement of  $\nu$  vs  $\bar{\nu}$  oscillation
  - Magnetized far detector: atm.  $\nu$ 's.
  - Likely eventual measurement with beam



Near Detector: 980 tons  
Far Detector: 5400 tons




# Neutrinos at the Main Injector (NuMI)



- 120 GeV protons
- 1.9 second cycle time
- $4 \times 10^{13}$  protons/pulse
- 0.4 MW!
- Single turn extraction ( $10 \mu\text{s}$ )
- $4 \times 10^{20}$  protons/year
- 700 m x 2 m diameter decay pipe for neutrino beam.
- 200 m rock absorber.
- Near detector complex.

# Status of NuMI Beamline Construction

- The excavation of the NuMI beamline halls and tunnels is ~complete.
- Outfitting and installation of beamline components will take about two years.
- **First protons on target expected in December 2004.**



# The NuMI Decay Tunnel



# The Decay Pipe

- Installation of the decay pipe is underway.
- Pipe is installed, welded, and concrete shielding is poured into place around it.
- Work is proceeding on schedule and should be complete this fall.



The first section of decay pipe is hoisted into place.

# Fabrication and Testing of Horns

Horn 2 inner conductors.




- The prototype upstream horn has been tested for 8 million pulses (80% of a NuMI year) with no problems.
- Both the final upstream horn and the downstream horn are now in fabrication.
- Target design is complete and fabrication is beginning.



Prototype horn 1 in test stand

# The NuMI Neutrino Energy Spectra



$\nu_{\mu}$  CC Events/kt/year

Low	Medium	High
470	1270	2740

$\nu_{\mu}$  CC Events/MINOS/2 year

Low	Medium	High
5080	13800	29600


$4 \times 10^{20}$  protons on target/year  
 $4 \times 10^{13}$  protons/1.9 seconds

By moving the horns and target, different energy spectra are available using the NuMI beamline. The energy can be tuned depending on the specific oscillation parameters expected/observed.



# The MINOS Far Detector

- 8m octagonal steel & scintillator tracking calorimeter
  - Sampling every 2.54 cm
  - 4cm wide strips of scintillator
  - 2 sections, 15m each
  - 5.4 kton total mass
  - $55\%/\sqrt{E}$  for hadrons
  - $23\%/\sqrt{E}$  for electrons
- Magnetized Iron ( $B \sim 1.5T$ )
- 484 planes of scintillator
  - 26,000 m<sup>2</sup>



One Supermodule of the Far Detector...  
Almost a "snapshot" of how the detector looks now!

# Detector Technology

- Scintillator strips are extruded polystyrene (Itasca Plastic)

- PPO (1%) and POPOP (0.03%) fluors

- Co-extruded  $\text{TiO}_2$  reflective coating

- Fiber groove



- Kuraray 1.2mm WLS Fibers
- (Y-11 175ppm)

- PMTs:



- Far Detector: Hamamatsu R6000-M16 multi-anode PMTs (16 channels), 8 fibers/pixel.

- Near Detector: "M64", one fiber per pixel.

- Viking "VA"-based front-end electronics.




**Objects not to scale**



# Assembly and Testing at Soudan



- Scintillator system components are assembled at universities and shipped to Soudan.
- Steel and components are sent down the shaft.
- Scintillator modules are mapped at the factories and some at Soudan. Typical agreement within 1%.



# Plane Assembly



Steel Welded and modules placed.




Plane lifted to vertical

Crane carries plane down the hall for installation



6-8 Planes per week

FarDet Installation by Week





# Status of MINOS Construction





- The far detector is almost half built.
- The coil will be installed in the first supermodule in June and energized in July.
- The full detector will be complete by June 2003.
- Cosmic Ray data are being collected for calibration and commissioning.

# The Near Detector

- **3.8 x 4.8m** “octagonal” steel & scintillator tracking calorimeter
- Same basic construction, sampling and response as the far detector.
- No multiplexing in the main part of the detector due to small size and high rates.
  - Hamamatsu M64 PMT
  - Faster Electronics (QIE)
- **282 planes of steel**
- **153 planes of scintillator**





# Near Detector Assembly



- Assembly of near detector planes is now underway on the surface at Fermilab.
- All planes will be assembled on the surface and then transferred (one at a time) underground once the hall is ready. This will allow the ND to be commissioned in time for beam turn-on.

# The MINOS Calibration Detector



- A mini-version of the MINOS near and far detectors

- 1m x 1m x 3.7 m
- 60 planes x 24 strips/plane
- Readout technologies of both the near and far detectors

- Being exposed to electron, pion, proton and muon beams from 0.5-10 GeV/c momentum at the CERN PS.

- First data in 2001 up to 3.5 GeV using far detector readout.
- Data in 2002 up to 10 GeV and to compare near and far electronics.
- Additional running in 2003 with full near readout system.


- **Physics Goals:**

- EM and Hadron energy response
- EM and Hadron event topology
- Near/Far readout comparison




# Electron Response Results from Caldet

## Total MEU vs. Beam Momentum



Preliminary

## Resolution<sup>2</sup> vs. 1/Beam Momentum




“MEU”= Muon Energy Unit. It is the average detector response resulting from a  $\sim 2$  GeV/c muon crossing perpendicularly through a plane of scintillator, corrected for gain-variation and local light output. It is the fundamental “calibration unit” for MINOS.


Expected resolution,  $23\%/\sqrt{E}$   
constant term  $< 5\%$

# Hadron Topology Measurements in Caldet

Sample **Pion** Events




Sample **Proton** Events



# Hadron Response Results from Caldet


Pion MEU distributions

Proton MEU Distributions




# Cosmic Ray Muon in the Far Detector

- Downgoing Cosmic Ray Muon
- Current rate of CR muons  $\sim 2$  Hz
- Magnetic field not yet on (curvature measurable up to  $\sim 70$  GeV)







# Cosmic Ray Muon in the Far Detector

- Downgoing Cosmic Ray Muon
- Current rate of CR muons  $\sim 2$  Hz
- Magnetic field not yet on (curvature measurable up to  $\sim 70$  GeV)





# Cosmic Ray Muons in the Far Detector



# Calibrating With Cosmic Rays


- Cosmic ray muons are used to measure the light output of the scintillator system in all detectors.
- The cosmic-ray muons are used to intercalibrate the three detectors.
- “Clean” muons (no showers) are selected for light calibration and for each muon the light output is corrected for the pathlength to the equivalent light for 1 cm pathlength.
- PMT gains are corrected using light injection data.
- **On average  $\sim 8.5$  pe's/cm.**



Average light output for all detector planes.

# Time Resolution in the Far Detector

- The time resolution of the MINOS scintillator system is determined primarily by the decay time of the Y11 fluor in the WLS fiber  $\sim 8$  ns.
- The time resolution for each scintillator strip is expected to be  $\sim 2.5$  ns based on the photoelectron statistics for muons.
- Current measurement of resolution using downgoing muons in the far detector is  $\sigma = 2.6$  ns/plane.
- The direction of muons can be determined with  $\sim 10$  planes for contained vertex events.
- To distinguish upgoing from downgoing through-going muons  $\sim 20$  planes are needed.




Distribution of measured time residuals for muons Passing through all strips in the far detector. The Time resolution of 2.6 ns is calculated from this data.




# The First MINOS Neutrino Event!

- The first neutrino-induced event has recently been observed!
- Upgoing muon passing through about 3.5 m of the detector. ( $p_{\mu} > 1.9 \text{ GeV}/c$ )
- Magnetic field not on yet so no measurement of the momentum.




# And the Second!


- The second neutrino-induced event has recently been observed.
- Upgoing muon passing through about 5.6 m of the detector. ( $p_{\mu} > 3.0 \text{ GeV}/c$ )
- Magnetic field not on yet so no measurement of the momentum.
- Contained vertex event?



# On the Road to Contained Events



Reconstructed “vertices” for cosmic ray events which have a track that ends inside the detector. Most are clearly downgoing stopping muons. A few mis-reconstruct for known reasons (hardware and software commissioning) which will be fixed soon.




Example of one downgoing stopping muon which appears to have a vertex just inside the nominal fiducial volume of the detector. This was due to tracking software which is not yet completely commissioned.

# MINOS Physics Goals (by 2007)


- Demonstrate Oscillation Behavior
  - Precise measurement of CC energy distribution between near and far detector (2-4% sys. uncertainty in  $E_\nu$  per 2 GeV bin).
  - “Standard” or non-standard oscillations?
    - Can we see clear “oscillatory” behavior from the first osc. max?
    - Are there features in the energy spectrum not well described by a standard oscillation?
- Precise Measurement of Oscillation Parameters
- Precise Determination of Flavor Participation
  - Number of CC  $\nu_\mu$  events far/near  $\sim 2\%$ : Probability for  $\nu_\mu - \nu_x$  oscillation.
  - Number of CC  $\nu_e$  events far/near: Sensitive to  $\nu_\mu - \nu_e$  oscillation down to about 2%.
  - Number of NC events far/near: probability for  $\nu_\mu - \nu_{\text{sterile}}$  oscillation down to about 5%.
  - $\nu_\mu$ 's which disappear but don't appear as  $\nu_e$  or disappear to  $\nu_{\text{sterile}}$  **must** be  $\nu_\tau$ !
- Direct Measurement of Atmospheric  $\nu$  vs  $\bar{\nu}$ .

# Topology of Neutrino Events


Identified by a relatively long track in an event. At very low energies, there can be some BG from NC  $\pi$ .



Identified by lack of a long track and a relatively concentrated EM shower in the core. Main BG comes from NC  $\pi^0$  events. From higher energy  $\nu$ 's.




Identified by lack of a long track and lack of strong EM core. Some high  $\gamma$  CC events are BG.



The Near Detector provides the ability to make statistical identification of events with high precision.

# Measurement of Oscillations in MINOS


CC energy distributions – Ph2le, 10 kt.yr.,  $\sin^2(2\theta)=0.9$



Note: MINOS beam results are presented for only 2 years of running! Longer-term running is certainly possible, even probable. Results are statistics limited.

# Appearance of Electrons

10 kT Years of data  
 $\nu_e$  Appearance



- Sensitivity is determined by statistical fluctuation of the NC  $\pi^0$  BG in the far detector.
- Limit on  $|U_{e3}|^2$  will scale like  $1/\sqrt{N}$  and is not limited by systematics for any realistic exposure.
- Limit can be further improved by removing high-energy tail from the NuMI beam and increased proton flux in later years.
- Ultimate MINOS limits  $\sim 1/3$  as shown here assuming extended running.

# Atmospheric Neutrino Measurements

- MINOS is the first large underground detector which has a magnetic field.
  - Measure charge/momentum of muons from  $\sim 0.5$ -70 GeV/c momentum.
  - Events with the neutrino interaction in the detector but where the muon exits still have complete  $E_\nu$  measurement: L/E measurements.
- Event direction reconstructed using timing and topology.
- Able to identify CC  $\nu_\mu$  and  $\bar{\nu}_\mu$  events from NC and CC  $\nu_e$  events over a very broad energy range as long as  $p_\mu > \sim 1$  GeV/c.
- We can directly compare whether atmospheric  $\nu_\mu$  and  $\bar{\nu}_\mu$  oscillate in the same way.
- Expected sensitivity is being calculated. Statistics for 24 kT years (end of 2007) are:

Number of Events in 24 kT years	Neutrino	Anti-Neutrino
Reconstructed Contained Vertex with muon	620	400
Reconstructed Upgoing Muon	280	120



# Conclusions

- The MINOS Detectors together with the NuMI beam will permit a next step in precision measurements of “atmospheric” neutrino oscillations:
  - Precise energy distribution... Showing the oscillation signature (?)
  - Precise measurement of  $\Delta m^2$
  - Precise determination of participation of different neutrino flavors
  - Extend sensitivity for small  $\nu_\mu - \nu_e$  mixing
  - Measurement of anti-neutrino mixing for atmospheric neutrinos
- Construction of the MINOS far detector is ~half complete and cosmic ray data is being accumulated with installed planes.
- Construction of the NuMI beamline is well underway. The tunnel excavation is complete. Remaining construction work on schedule.
- Data acquisition for cosmic rays and atmospheric neutrinos underway!
- First protons on target scheduled for December 2004.
- Count on more than two years of beam data from MINOS!