

# The T2K Neutrino Beamline


Mark Hartz

[mhartz@physics.utoronto.ca](mailto:mhartz@physics.utoronto.ca)

University of Toronto/York University  
for the T2K Collaboration




# T2K Experiment



- Neutrino beam produced at J-PARC using 30 GeV proton synchrotron
- Far detector is Super-K 50 kton water Cherenkov detector
- Near detector at 280 m downstream neutrino production target is currently being built
- Detectors located 2.5 degrees off-axis – narrower energy distribution with peak at oscillation maximum ( $\sim 700$  MeV)

# J-PARC Accelerator Complex



280 m on-axis and off-axis neutrino detectors

Neutrino target hall, decay volume, muon detector


## Accelerator Complex Schedule:

- Linac, RCS – 2007
- Main Ring – 2008
- Neutrino – 2009

## Accelerator Design/Performance

- Design goal of 750 kW
- Will be achieved at 30 GeV
- $4 \times 10^{11}$  p single shot mode for beamline commissioning (0.3 kW at 6 sec. Period)
- Details on continuous/high power beam configurations on later slide

# T2K Beamline



# Status and Goals for Commissioning

- Major goal for spring 2009 commissioning was passing a Japanese government inspection for radiation safety (inspection was passed)
- Additional goals included:
  - Studies of neutrino beamline tunings
  - Study performance of beamline components
- Constraint - minimize radioactivation of beamline areas to allow for summer work
- Status of beamline for commissioning:
  - All magnets fully operational
  - All beamline monitors and muon monitor functioning
  - First horn installed
  - One module for INGRID (280 m on-axis detector) installed
  - GPS and triggering at Super-K operational
- Two spring commissioning runs – April 23rd-28th, May 22nd-28th.

# Beamline Components

# Beamline Magnets

## Superconducting Magnets

- Located in the arc section of the beamline
- 28 magnets each producing both dipole (2.59 T) and quadrupole (18.6 T/m) fields
- Operational current of 4.36 kA,  $T_{\max} < 5$  K
- 2 hour recovery from normal quench




## Normal Conducting Magnets

- Located in the preparation and final focusing sections of the beamline
- Operate in the 1-10 kG range

# CT and Beam Loss Monitors

## Current Transformer (CT) Monitors

- 5 monitors spaced throughout the T2K beamline
- Linear response up to 90A
- Flat response in 1 kHz-60 MHz range




## Beam Loss Monitors

- 40 Gas filled proportional counters
- Can observe a wide range of beam loss
- TLD badges placed near BLMs for calibration during commissioning



# Position and Profile Monitors




## Segmented Secondary Emission Profile Monitor (SSEM)

- 19 monitors throughout beamline
- Current induced by beam incident on cathode strips
- Each monitor has X and Y oriented strips
- Expected uncertainty of 0.2 mm or less
- Will be pulled out for high intensity running

## ElectroStatic Beam Position Monitor (ESM)



- 21 monitors located near SSEMs
- Nondestructive measurement
- Four electrodes measure beam field
- Find beam position by comparing signal sizes
- Design resolution of 0.5 mm



# OTR and Horns

## Optical Transition Radiation Monitor


- Beam crosses foil to produce optical transition radiation or fluorescent light
- Light is imaged using system of parabolic mirrors and camera
- Image shows profile of proton beam
- Located 280 mm upstream of target



## Target + Magnetic Horns

- Helium cooled graphite target
- Three magnetic horns focus the hadrons produced at the target
- Nominal currents of 320 kA
- For commissioning only first horn at 273 kA

# Decay Volume and Muon Monitor




## Decay Volume and Beam Dump

- ~100 m decay volume after target station
- Water cooled graphite block beam dump at end of decay volume

## MUMON Muon Monitor


- Located downstream of beam dump
- Silicon PIN photodiodes
- Ionization chamber
- Measures secondary muons from pion decays
- >5 GeV muons make it through beam dump (looking at tail of distribution)
- Determine beam position and direction along with SSEM, ESM and OTR



# Commissioning Experiences/Highlights

# Commissioning Firsts


## First beam with super conducting and NC dipole magnets




# MUMON and Emulsion Studies

## MUMON SI Profiles

### Horn off




### Horn at 273 kA




- See peaks in MUMON
- Positions correlate well with profile monitors
- Total charge increases with Horn 1 focusing

## Emulsion Plates Downstream of MUMON




- Placed emulsion plates immediately behind MUMON to verify muon
- Can separate mu/e to get muon flux
- Inserted for three separate spills
- Analysis is ongoing

Emulsion data



# Preliminary Alignment Studies

ESM18 vs SSEM16 y




Preliminary studies of monitor correlations show no major surprises

Detailed studies ongoing



See good agreement for beam position at center of target as measured by OTR and MUMON

Preliminary




# ESM and SE Electrons

- Anomalous waveforms seen for ESMs during commissioning



- Only seen when SSEMs are inserted
- Best hypothesis – due to secondary emission electrons from the SSEMs
- Hardware fix under investigation – wrap solenoid around the ESM to steer away electrons





# Summary of Accomplishments


- Stability of the extraction beam orbit from Main Ring is confirmed
- Combined function superconducting magnets work as expected
- Beam is transported to center of T2K target with no significant beam loss
- Beam tuned to within 3 mm w.r.t the design orbit
- Functionality of the beamline monitors confirmed
- Neutrino production and pion focusing by the horn confirmed by MUMON signal
- Stable beam during continuous operation within 1 mrad as measured by MUMON
- Intentional quench of 4 superconducting magnets, recovery in 2 hrs
- Additional beam configurations:
  - Power: 1.13 kW operation for 30 seconds (6sec/cycle, 2 bunches,  $7.1 \times 10^{11}$  protons/bunch)
  - Duration: 0.14 kW operation for 40 minutes (6sec/cycle, 1 bunch,  $1.7 \times 10^{11}$  protons/bunch)

# Moving Forward

- Next beam commissioning run begins later this year
  - In June, accelerator team already achieved 6 bunch operation
- Preparation for multi-bunch and 100 kW operation
- Horn 2 recently installed and Horn 3 will be installed soon
- On-axis (INGRID) detector at 280 m installation is ongoing and will be complete before next round of commissioning
  - Goal of direct confirmation of neutrino production
- Be ready for physics run by December 2009!


# Extra Slides

# OTR Detector




- Use optical transition radiation to monitor beam near target
- Produced when particles moves between media with different dielectric constants – radiates difference in E field

Rad-hard camera  
up to 10 kGy




# Emulsion Details




Emulsion scanning at LHEP  
Bern

# SSEM vs OTR Correlations

Preliminary



Preliminary



Offset understood as difference in alignment coordinate systems